

LIST OF QUANTITIES

Item Number	Description	Units	Construction Type Code		
			1000	Y031- TF	Non Part
20200100	Earth Excavation	C.Y.	749		
20800150	Trench Backfill	C.Y.	2,490		
21001000	Geotechnical Fabric for Ground Stabilization	S.Y.	3,986		
25200100	Sodding	S.Y.	1,643		
28000500	Inlet and Pipe Protection	Each	25		
35100100	Aggregate Base Course, Type A	Ton	1,397		
40600100	Bituminous Materials (Prime Coat)	Gal.	323		
40600400	Mixture For Cracks, Joints, And Flangeways	Ton	5		
40600625	Leveling Binder (Machine Method) N50	Ton	1,666		
40603335	Hot-Mix Asphalt Surface Course Mix "D" N50	Ton	1,466		
40800050	Incidental Hot-Mix Asphalt Surfacing	Ton	6		
42300200	PCC Driveway Pavement, 6"	S.Y.	312		
42300300	PCC Driveway Pavement, 7"	S.Y.	135		
42400200	PCC Sidewalk, 5"	S.F.	18,974		
42400800	Detectable Warnings	S.F.	336		
44000080	Hot-Mix Asphalt Surface Removal (Cold Milling)	S.Y.	5,730		
44000100	Pavement Removal	S.Y.	3,733		
44000200	Driveway Pavement Removal	S.Y.	468		
44000500	Combination Curb & Gutter Removal	Ft.	2,334		
44000600	Sidewalk Removal	S.F.	18,796		
44400100	Fiberglass Fabric Repair System	S.Y.	140		
55100500	Storm Sewer Removal, 12"	Ft.	100		
* 56100600	Watermain, 6"	Ft.			265
* 56100700	Watermain, 8"	Ft.			537
* 56100800	Watermain, 10"	Ft.			3,218
* 56200200	Water Service Line, 3/4"	Ft.			366
* 56201300	Corporation Stops, 3/4"	Each			54
* 56400500	Fire Hydrant to Be Removed	Each			8
* 56400600	Fire Hydrant	Each			9
* 56500600	Domestic Water Service Boxes To Be Adjusted	Each	5		
60218400	Manhole, Type A, 4' Diameter, Type 1 Frame, Closed Lid	Each	8		
60221100	Manhole, Type A, 5' Diameter, Type 1 Frame, Closed Lid	Each	2		
60226400	Manhole, Drop Type, 4' Diameter, Type 1 Frame, Closed Lid	Each	2		
60255500	Manhole, to Be Adjusted	Each	11		
60255800	Manhole, to Be Adjusted, With Type 1 Frame, Closed Lid	Each	5		
60266910	Valve Box To Be Removed	Each	17		
60500040	Removing Manhole	Each	8		
60500070	Removing Manhole To Maintain Flow	Each	12		
60500080	Removing Catch Basin To Maintain Flow	Each	26		
60610100	Combination Concrete Curb & Gutter, Type M-6.18 (Modified)	Ft.	2,334		
67100100	Mobilization	L.S.	1		
70103700	Traffic Control Complete	L.S.	1		
70300200	Temporary Pavement Marking	Ft.	4,642		
70301000	Work Zone Pavement Marking Removal	S.F.	2,321		
70400100	Temporary Concrete Barrier	Ft.	125		
* 78000100	Thermoplastic Pavement Marking- Letters and Symbols	S.F.	83		

* Specialty Items

LEGEND

	EXISTING DECIDUOUS TREE
	EXISTING EVERGREEN TREE
	EXISTING BUSH
	EXISTING SIGN
	EXISTING DOMESTIC SERVICE VALVE
	EXISTING WATER VALVE
	PROPOSED WATER VALVE
	EXISTING FIRE HYDRANT
	PROPOSED FIRE HYDRANT
	EXISTING GAS VALVE
	EXISTING POWER POLE
	EXISTING LIGHT POLE
	EXISTING TRAFFIC SIGNAL
	EXISTING TRAFFIC SIGNAL MAST ARM
	PROPOSED VIDEO DETECTOR
	EXISTING HANDHOLE
	EXISTING TRAFFIC SIGNAL CONTROLLER
	EXISTING SINGLE CATCH BASIN
	EXISTING DOUBLE CATCH BASIN
	EXISTING SANITARY MANHOLE
	EXISTING SANITARY CLEANOUT
	EXISTING STORM MANHOLE
	EXISTING WATER MANHOLE
	EXISTING TELEPHONE MANHOLE
	EXISTING SANITARY SEWER
	PROPOSED SANITARY SEWER
	EXISTING STORM SEWER
	PROPOSED STORM SEWER
	EXISTING WATER MAIN
	PROPOSED WATER MAIN
	EXISTING GAS MAIN
	EXISTING ELECTRICAL CONDUIT
	EXISTING FIBER OPTIC CONDUIT
	EXISTING TELEPHONE CONDUIT
	EXISTING R.O.W. LINE
	BITUMINOUS SURFACE REMOVAL
	PAVEMENT REMOVAL & PCC BASE COURSE
	PAVEMENT REMOVAL & PCC PAVEMENT
	SIDEWALK REMOVAL & REPLACEMENT
	PCC CURB RAMP
	PCC TEXTURED PAVEMENT & PCC TEXTURED MEDIAN
	PCC DRIVEWAY REMOVAL & REPLACEMENT
	PCC CURB AND GUTTER REMOVAL & REPLACEMENT
	DETECTABLE WARNINGS

85434
L.A. # 06-00180-00-RS
QUANTITIES & LEGEND

CITY OF ROCK ISLAND	
ENGINEERING DIVISION	
24th Street Resurfacing	
18th Avenue to 31st Avenue	
Job Number	Date
2569	April 5, 2007
Computer Drawing Name	By
2569 QtyLog.dwg	mdw
	Sheet
	3
	Of
	38