



- ① RT. STA. 0+20 TO STA. 0+35 (BROADWAY AVE.)
LT. STA. 0+36.5 TO STA. 0+51.50 (BROADWAY AVE.)
REMOVE EXISTING SIDEWALK AND CONCRETE CURB
CONSTRUCT CURB RAMPS FOR SIDEWALKS TYPE B
SIDEWALK REMOVAL
CURB REMOVAL
DETECTABLE WARNINGS
PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH
- ② STA. 0+33 AND STA. 0+38 (BROADWAY AVE.)
REMOVE EXIST. PAVT. MARKINGS FOR CROSSWALK
PAVEMENT MARKING REMOVAL
- ③ LT. STA. 0+86
REMOVE EXIST. 12" CONC. STORM SEWER
PLUG 1" AT EXIST. 24" CONC. STORM SEWER
USING CLASS SI CONC. COST TO BE INCLUDED
IN STORM SEWER REMOVAL 12"
- ④ LT. STA. 0+80 TO LT. STA. 0+86
REMOVE EXISTING CONCRETE CURB AND GUTTER
COMBINATION CURB AND GUTTER REMOVAL
- ⑤ LT. STA. 0+05 TO STA. 2+02
EXISTING 20" DIA. COMBINED SEWER
TO BE REMOVED
20" COMBINED SEWER REMOVAL
- ⑥ RT. STA. 0+94 TO STA. 1+10
REMOVE EXISTING SIDEWALK
SIDEWALK REMOVAL
- ⑦ RT. STA. 1+11 TO STA. 1+59 AND STA. 1+73 TO STA. 2+00
REMOVE EXISTING BITUMINOUS PAVEMENT
PAVEMENT REMOVAL
- ⑧ 3.0' RT. AND 11.0' LT. OF STA. 0+00.5 TO STA. 0+10.5
REMOVE EXISTING SIDEWALK
SIDEWALK REMOVAL
- ⑨ EXISTING WATER SERVICES TO BE ADJUSTED
BY ILLINOIS AMERICAN WATER CO.

REVISIONS

SMS Sheppard, Morgan & Schwaab, Inc.
ENGINEERS
CONSULTING ENGINEERS AND LAND SURVEYORS
215 Market Street, P.O. Box E, Alton, IL 62002 618462-9765 E-mail: mail@smsengineers.com
10 Central Industrial Drive, Granite City, IL 62040 618477-8700 E-mail: mail@graniteengineers.com
DESIGN FIRM # 184-000992

ALTON, ILLINOIS
PEDESTRIAN OVERPASS AT LANGDON ST.
DEMOLITION PLAN

S:\and projects\ALTON_406924_1\img\Demolition Plan.dwg 5/12/2008 8:51:43 AM, J:\man, 120