



SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | TOTAL | URBAN | |
|------------|---|--------|-------|---|--------------------|
| | | | | HBP FUNDING 80% FEDERAL 20% STATE | |
| | | | | CONSTRUCTION TYPE CODE | |
| | | | | BRIDGE X020-2A | ROADWAY 1000-2A |
| 550A0450 | STORM SEWERS, CLASS A, TYPE 2 36" | FOOT | 71 | 71 | |
| 55101600 | STORM SEWER REMOVAL 36" | FOOT | 4 | 4 | |
| 59100100 | GEOCOMPOSITE WALL DRAIN | SQ YD | 62 | 62 | |
| 60100060 | CONCRETE HEADWALL FOR PIPE DRAINS | EACH | 3 | 3 | |
| 60100945 | PIPE DRAINS 12" | FOOT | 41 | 41 | |
| 60109580 | PIPE UNDERDRAINS FOR STRUCTURES 4" | FOOT | 192 | 192 | |
| 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 1 | 1 | |
| 60221100 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 1 | 1 | |
| 61000115 | TYPE E INLET BOX, STANDARD 610001 | EACH | 2 | 2 | |
| * 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 275 | 275 | |
| * 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 2 | 2 | |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 4 | 4 | |
| * 63100205 | TRAFFIC BARRIER TERMINAL, TYPE 5A (SPECIAL) | EACH | 1 | 1 | |
| * 63100215 | TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL) | EACH | 2 | 2 | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 360 | 360 | |
| * 63300725 | STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS) | FOOT | 25 | 25 | |
| 66201120 | CONCRETE SHOULDER CURB | FOOT | 22.2 | 22.2 | |
| 66410400 | CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED | FOOT | 441 | | 441 |
| 66600105 | FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS | EACH | 10 | 7 | 3 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 9 | 9 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | 1 | |
| 70101205 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL) | EACH | 1 | 1 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 25 | 25 | |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 1 | 1 | |
| 70106700 | TEMPORARY RUMBLE STRIP | EACH | 6 | 6 | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 8 | 8 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 544 | 544 | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 68 | 68 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 4540 | 2543 | 1997 |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 105 | | 105 |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 45 | 45 | |

SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | TOTAL | URBAN | |
|------------|---|-------|-------|---|--------------------|
| | | | | HBP FUNDING 80% FEDERAL 20% STATE | |
| | | | | CONSTRUCTION TYPE CODE | |
| | | | | BRIDGE X020-2A | ROADWAY 1000-2A |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 2082 | 1311 | 771 |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 412.5 | 412.5 | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 262.5 | 262.5 | |
| * 78001100 | PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 68 | 68 | |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 4540 | 2543 | 1997 |
| * 78001150 | PAINT PAVEMENT MARKING - LINE 12" | FOOT | 105 | | 105 |
| * 78001180 | PAINT PAVEMENT MARKING - LINE 24" | FOOT | 45 | 45 | |
| 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 21 | 21 | |
| * 78200530 | BARRIER WALL MARKERS, TYPE C | EACH | 6 | 6 | |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | 4 | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 175 | 175 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 11 | 6 | 5 |
| * 80300100 | LOCATING UNDERGROUND CABLE | FOOT | 500 | 500 | |
| * 81200120 | CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL | FOOT | 78 | 78 | |
| 86200300 | UNINTERRUPTIBLE POWER SUPPLY, EXTENDED | EACH | 1 | 1 | |
| X0325326 | TEMPORARY TRAFFIC CONTROL REMOVAL | L SUM | 1 | 1 | |
| X5020501 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1 | EACH | 1 | 1 | |
| X5020502 | UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2 | EACH | 1 | 1 | |
| Z0001900 | ASBESTOS BEARING PAD REMOVAL | EACH | 22 | 22 | |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | |

*SPECIALITY ITEM

| | | | | |
|---------------------|-----------|------------------|--------------|-----------|
| CONTRACT NO. 98999 | | | | |
| FAP RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 869 | (105A)B-1 | SALINE | 71 | 4 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

ESCA
CONSULTANTS, INC.

| | | |
|--------------|---------|-------|
| DESIGNED BY: | MTD | 06/07 |
| DRAWN BY: | DWH/HAS | 03/08 |
| CHECKED BY: | MTD | 03/08 |
| APPROVED BY: | RPD | 03/08 |

PLOT DATE = \$DATE\$
FILE NAME = \$FILEL\$
PLOT SCALE = \$SCALE\$
REFERENCE = \$REF\$

SUMMARY OF QUANTITIES
FAP RTE 869 (IL 34)
SECTION (105A)B-1
SALINE COUNTY