



FAP RTE	SECTION	COUNTY	TOTAL SHEETS	NO.
869	(105A)B-1	SALINE	71	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**DRAINAGE SCHEDULE**

LOCATION	PIPE CULV. CL. A.		STORM SEWERS CL. A. TYPE 2		PIPE DRAINS 12"	END SECTIONS 12"	PRC FLARED END SECTIONS		REINFORCED CONCRETE PIPE ELBOW 36"	MANHOLES, TYPE A		TYPE E INLET BOX STD 610001	CONC SHLD CURB	PROTECTIVE COAT	CONC COLLAR	PIPE UNDERDRAINS FOR STRUCTURES 4"	CONCRETE HEADWALL FOR PIPE DRAINS		
	TYPE 1 24"	TYPE 2 24"	18"	36"			EACH	EACH		EACH	EACH							EACH	EACH
	FOOT	FOOT	FOOT	FOOT															
1646+05.0, 67.0' RT							1												
1646+06.9, 62.3' LT	10						1												
1646+13.0, 54.4' LT															0.44				
1646+50.0, 67.0' RT		90					1												
1646+95.0, 67.0' RT															0.44				
1646+98.2, 55.3' RT																			
1647+00.0, 57.7' RT	4						1												
1648+58.7, 39.0' LT																	1		
BEHIND NORTH ABUTMENT																89			
1649+00.8, 39.0' RT																	1		
1649+25.5, 45.0' LT								1											
1649+41.8, 39.0' LT																	1		
BEHIND SOUTH ABUTMENT																103			
1649+61.2, 34.0' RT				11				1											
1649+74.8, 28.0' RT									1						0.66				
1649+77.0, 45.0' LT			10	49	9					1									
1649+79.64, 33.58' LT											1	12.2	9.5						
1649+79.8, 59.0' RT						1													
1649+85.1, 54.5' LT															0.30				
1649+91.3, 52.8' RT					32					1									
1649+91.7, 36.7' LT				11						1				0.66					
1650+03.21, 32.74' RT											1	10.0	9.5						
TOTALS	14	90	10	71	41	1	4	2	2	1	1	2	22.2	19.0	2.50	192	3		

**PAVEMENT MARKER REMOVAL SCHEDULE**

LOCATION	RRPM REMOVAL
	EACH
STA 1643+20	1
STA 1644+00	1
STA 1644+82	1
STA 1645+61	1
STA 1646+41	1
STA 1647+21	1
STA 1648+01	1
STA 1648+81	1
STA 1649+62	1
STA 1650+42	1
STA 1651+25	1
TOTAL	11

**CHAIN LINK FENCE SCHEDULE**

LOCATION	TO BE REMOVED AND RE-ERECTED
	FOOT
1642+00, 57' RT TO 75' RT	18
1642+00 TO 1644+50, 75' RT	250
1644+50, 75' RT TO 85' RT	10
1644+50 TO 1646+12.5, 85' RT	163
TOTAL	441

**WORK ZONE AND PAVEMENT MARKING REMOVAL SCHEDULE**

LOCATION	PAVEMENT MARKING DESCRIPTION	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
		SQ FT	SQ FT
1644+65 TO 1652+10, C	EX SKIP-DASH		65
1646+25 TO 1648+54, RT	EX EDGELINE		35
1650+03 TO 1651+04, LT	EX EDGELINE		75
VARIOUS	SHORT-TERM	181.5	
VARIOUS	TEMPORARY	1513.5	
TOTALS		2,082.0	175

**GUARDRAIL REMOVAL SCHEDULE**

LOCATION	FOOT
STRUCTURE NO. 083-0041 - NE	105
STRUCTURE NO. 083-0041 - NW	102
STRUCTURE NO. 083-0041 - SE	65
STRUCTURE NO. 083-0041 - SW	88
TOTAL	360

**FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS SCHEDULE**

LOCATION	EACH
1642+00.00, 40.45' RT	1
1642+00.00, 75.00' RT	1
1642+00.00, 39.55' LT	1
1642+00.00, 75.00' LT	1
1644+50.00, 75.00' RT	1
1644+50.00, 85.00' RT	1
1649+15.00, 75.00' LT	1
1649+15.00, 56.00' LT	1
1649+73.00, 56.00' LT	1
1649+93.66, 80.64' LT	1
TOTAL	10

**PAVEMENT REMOVAL SCHEDULE**

LOCATION	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL
	SQ YD	SQ YD
NORTH BRIDGE APPROACH	147	
SOUTH BRIDGE APPROAH	137	
1646+50, CE RT		107
SMALL STREET - 42+06.5, CE RT		126
SMALL STREET - 44+40, CE RT		93
DORRIS HEIGHTS ROAD - 45+60 TO 46+16, RT	16	
TOTALS	300	326

**PIPE REMOVAL SCHEDULE**

LOCATION	CLASS D PATCHES, TYPE IV, 6 INCH	STORM SEWER REMOVAL 36"	PIPE CULVERT REMOVAL
	SQ YD	FOOT	FOOT
1646+50, CE RT	56		84
1649+74.8, 28.0' RT		4	
1649+80.8, 49.7' LT			5
1649+91.7, 36.7' LT			8
TOTALS	56	4	97

**BRIDGE APPROACH PAVEMENT SCHEDULE**

LOCATION	BRIDGE APPROACH PAVEMENT			PROTECTIVE COAT
	STD	(SPECIAL)	CONNECTOR (FLEXIBLE)	
	SQ YD	SQ YD	SQ YD	
NORTH APPROACH	178	18	181	
SOUTH APPROACH		188	22	190
TOTALS	178	188	40	371

**HMA SURF REMOVAL SCHEDULE**

LOCATION	BUTT JOINT
	SQ YD
1642+95	87
TOTAL	87

SCHEDULE OF QUANTITIES  
 FAP RTE 869 (IL 34)  
 SECTION (105A)B-1  
 SALINE COUNTY



DESIGNED BY: MTD 03/08  
 DRAWN BY: DWH/HAS 03/08  
 CHECKED BY: MTD 03/08  
 APPROVED BY: RDP 03/08

PLOT DATE = #DAYS  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#