

**SUMMARY OF QUANTITIES**

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL ESTIMATED QUANTITY	AS-BUILT QUANTITY
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	1,400	
AR152460	TOPSOIL STRIPPING	C.Y.	4,100	
AR152441	ON-SITE BORROW	C.Y.	14,500	
AR155712	LIME-MODIFIED SUBGRADE - 12"	S.Y.	12,200	
AR209608	CRUSHED AGG. BASE COURSE - 8"	S.Y.	12,250	
AR209612	CRUSHED AGG. BASE COURSE - 12"	S.Y.	235	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	1,650	
AR501514	14" PCC PAVEMENT	S.Y.	11,100	
AR501518	18" PCC PAVEMENT	S.Y.	700	
AR501530	PCC TEST BATCH	EACH	1	
AR501900	REMOVE PCC PAVEMENT	S.Y.	2,900	
AR501910	REMOVE & REPLACE PCC PAVEMENT	S.Y.	750	
AR605541	CLEAN & SEAL CRACKS	L.F.	2,000	
AR162506	CLASS E FENCE 6'	L.F.	600	
AR162900	REMOVE CLASS E FENCE	L.F.	800	
AR701512	12" RCP, CLASS IV	L.F.	120	
AR701524	24" RCP, CLASS IV	L.F.	325	
AR701900	REMOVE PIPE	L.F.	250	
AR705526	6" PERFORATED UNDERDRAIN W/ SOCK	L.F.	1,100	
AR751540	MANHOLE 4'	EACH	1	
AR751550	MANHOLE 5'	EACH	1	
AR751803	UNDERDRAIN CLEANOUT	EACH	4	
AR751903	REMOVE MANHOLE	EACH	2	
AR751906	REMOVE CATCH BASIN	EACH	1	
AR751943	ADJUST MANHOLE	EACH	1	
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	2	
AR752424	PRECAST REINFORCED CONC. FES 24"	EACH	3	
AR752903	REMOVE HEADWALL	EACH	3	
AR754904	REMOVE COMB CURB & GUTTER	L.F.	300	
AR801510	SEEDING	ACRE	1.8	
AR108108	1/C #8 5 KV UG CABLE	L.F.	1,600	
AR108706	1/C #6 COUNTERPOISE	L.F.	800	
AR110202	2" PVC DUCT, DIRECT BURY	L.F.	1,000	
AR110508	8-WAY CONCRETE ENCASED DUCT	L.F.	350	
AR110610	ELECTRICAL HANDHOLE	EACH	4	
AR125415	MIL-BASE MOUNTED	EACH	13	
AR125442	TAXIWAY GUIDANCE SIGN, 2 CHARACTER	EACH	1	
AR125445	TAXIWAY GUIDANCE SIGN, 5 CHARACTER	EACH	1	
AR150520	MOBILIZATION	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR156510	SILT FENCE	L.F.	800	
AR156511	DITCH CHECK	EACH	1	
AR156520	INLET PROTECTION	EACH	5	
AR156532	EXCELSIOR BLANKET	S.Y.	8,700	
AR156540	RIPRAP	S.Y.	140	
AR801700	REMOVE GUARDRAIL	L.F.	30	
AR801701	ECONCRETE BASE COURSE - 6"	S.Y.	11,950	
AR801702	PART DEPTH PCC PAVT. REPAIR - 2"-4"	S.F.	250	
AR801703	PART DEPTH PCC PAVT. REPAIR - 4"-6"	S.F.	250	
AR801704	PCC PANEL REINFORCEMENT (SPECIAL)	S.Y.	750	
AR801705	RELOCATE STORAGE TANKS	L.S.	1	

**PE087**



850 East Diehl Road  
Suite 120  
Naperville, Illinois 60563  
630-505-1991 FAX 630-505-1977  
www.rsandh.com



**TERMINAL  
APRON  
EXPANSION**

**SUBCONSULTANTS**

PSA Dewberry

STS | AECOM

IL PROJECT: PIA-3812  
AIP PROJECT: 3-17-0080-46

**REVISIONS**

NO.	DESCRIPTION	DATE

DATE ISSUED: 06/27/08  
REVIEWED BY: PCB  
DRAWN BY: MJL  
DESIGNED BY: NDO

**AEP PROJECT NUMBER  
213-6945-000**

© 2008 REYNOLDS, SMITH AND HILLS INC.

**SHEET TITLE**

**SUMMARY OF  
QUANTITIES**

**SHEET NUMBER**

**2 OF 43**

**ISSUED FOR  
BID DOCUMENTS**