

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 ROADWAY 100% STATE						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 ROADWAY 100% STATE					
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	3824	3824						44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	75	75					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10						44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	125	125					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	468	468						44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	60	60					
X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	200	200						48101200	AGGREGATE SHOULDERS, TYPE B	TON	140	140					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	65	65						48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	105	105					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	80	80						63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	25	25					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	809	809						63200310	GUARDRAIL REMOVAL	FOOT	25	25					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	8249	8249						63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE I	EACH	1	1					
44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SO YD	286	286						67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
										67100100	MOBILIZATION	L SUM	1	1					
										70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
										70300100	SHORT TERM PAVEMENT MARKING	FOOT	3263	3263					
										70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	73	73					

* SPECIALTY ITEMS