

SUMMARY OF QUANTITIES				URBAN CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				URBAN CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	14.7	14.7					44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	36675	36675						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	201	201					44000600	SIDEWALK REMOVAL	SO FT	3803	3803						
25200110	SODDING, SALT TOLERANT	SO YD	201	201					44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	15	15						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	56	56					44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	20	20						
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, NSO	TON	1513	1513					44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	35	35						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	50	50						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	653	653					44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	30	30						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3081	3081					60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE I FRAME, CLOSED LID	EACH	1	1						
42001300	PROTECTIVE COAT	SO YD	443	443					60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	6	6						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	3803	3803					60406000	FRAMES AND LIDS, TYPE I, OPEN LID	EACH	3	3						
42400800	DETECTABLE WARNINGS	SO FT	731	731					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
									67100100	MOBILIZATION	L SUM	1	1						
									70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1						