

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	80	80					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	228	228					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	439	439					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	10858	10858						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	974	974					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	245	245						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	500	500					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16050	16050						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	988	988					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	80	80						X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	24756	24756					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	228	228						X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1200	1200					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	439	439						X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	70	70					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	6695	6695						Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	90	90					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	245	245						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	58	58					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16050	16050															

URBAN

URBAN

*Specialty Items