

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	ROADWAY
				0005	URBAN
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5,439.4	5,439.4	
20400800	FURNISHED EXCAVATION	CU YD	10.0	10.0	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	9,259	9,259	
21400100	GRADING AND SHAPING DITCHES	FOOT	4,480	4,480	
25000210	SEEDING, CLASS 2A	ACRE	2	2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	173	173	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	173	173	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	173	173	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	192	192	
28000305	TEMPORARY DITCH CHECKS	FOOT	250	250	
28000400	PERIMETER EROSION BARRIER	FOOT	8,180	8,180	
28000510	INLET FILTERS	EACH	15	15	
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	9,259	9,259	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	12,290	12,290	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	21	21	

• SPECIALTY ITEMS

15

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: HRGreen.com
 DATE PLOTTED: 5/23/2014 11:055 AM
 FILE NAME: 661001%10-sum-01.dgn
 PLOT DRIVER: ltx17_dwg.plt
 PEN TABLE: standard.ctb



USER NAME * dntonez	DESIGNED - J. ATTANASEO	REVISED -
PLOT SCALE * N.T.S.	DRAWN - J. ATTANASEO	REVISED -
PLOT DATE * 5/23/2014	CHECKED - T. HAMILTON	REVISED -
	DATE - 5/23/14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
US ROUTE 12 (ELA RD. TO LAKE COOK RD.)			
SCALE: N.T.S.	SHEET NO. 1 OF 5 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	SY-3-RS-4	LAKE	104	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60N26	