

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				ROADWAY	
				0005	URBAN
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3	3	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	72	72	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	7,500	7,500	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,340	1,340	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,562	1,562	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	17,490	17,490	
42001300	PROTECTIVE COAT	SQ YD	195	195	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	21	21	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	100	100	
42400800	DETECTABLE WARNINGS	SQ FT	150	150	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	178,470	178,470	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	42	42	
44000600	SIDEWALK REMOVAL	SQ FT	250	250	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	6,970	6,970	

▪ SPECIALTY ITEMS

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: HRGreen.com
 DATE PLOTTED: 5/23/2014 12:02:24 PM
 FILE NAME: 6610019610-04-01.dwg
 PLOT DRIVER: HPGL_PLOTTER
 PEN TABLE: standard.tbl



USER NAME: *detanz
 PLOT SCALE: * N.T.S.
 PLOT DATE: * 5/23/2014

DESIGNED - J. ATTANASEO
 DRAWN - J. ATTANASEO
 CHECKED - T. HAMILTON
 DATE - 5/23/14

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 US ROUTE 12 (ELA RD. TO LAKE COOK RD.)
 SCALE: N.T.S. SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	SY-3-RS-4	LAKE	104	4
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 60N26