

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0004 80% FED 20% STATE ROADWAY	0021 80% FED 15% STATE 2.5% HOFFMAN ESTATES 2.5% STREAM- WOOD T. SIGNALS	0021 100% HOFFMAN ESTATES E.V.P.		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1				
20101000	TEMPORARY FENCE	FOOT	750	750				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	397	397				
20400800	FURNISHED EXCAVATION	CU YD	295	295				
20800150	TRENCH BACKFILL	CU YD	49	49				
21101635	TOPSOIL FURNISH AND PLACE, 9"	SQ YD	1018	1018				
25000210	SEEDING, CLASS 2A	ACRE	0.15	0.15				
25100630	EROSION CONTROL BLANKET	SQ YD	1018	1018				
28000400	PERIMETER EROSION BARRIER	FOOT	450	450				
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	647	647				
35600704	HOT-MIX ASPHALT BASE COURSE WIDENING, 7"	SQ YD	491	491				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8.5	8.5				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	226	226				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	104	104				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0004 80% FED 20% STATE ROADWAY	0021 80% FED 15% STATE 2.5% HOFFMAN ESTATES 2.5% STREAM- WOOD T. SIGNALS	0021 100% HOFFMAN ESTATES E.V.P.		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	528	528				
42001300	PROTECTIVE COAT	SQ YD	207	207				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	180	180				
42400800	DETECTABLE WARNINGS	SQ FT	20	20				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	4891	4891				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1				
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	82	82				
55106025	STORM SEWER INSTALLATION 12"	FOOT	41	41				
60107600	PIPE UNDERDRAINS 4"	FOOT	500	500				
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5	5				
60203905	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6	6				

FILE NAME *	USER NAME * gajlana01	DESIGNED -	REVISED -
c:\pwworking\pavlod\gajlana01\02483\1110109.plt		DRAWN -	REVISED -
PLOT SCALE * 100,0000 / 1 in		CHECKED -	REVISED -
PLOT DATE * 5/20/2004		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
BARRINGTON ROAD AT BODE ROAD			
SCALE: NONE	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
362	D105R-N121	COOK	48	3
CONTRACT NO. 60T96				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				