



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
ct:\pr-work\p1dot\pyrzenowski\b\0311620	pyrzenowski	-	R. MIRS 09-15-97
	D151112-sht-plan.dgn	DRAWN :	REVISED :
		-	R. MIRS 12-11-97
	PLOT SCALE = 100.000 / / in.	CHECKED :	REVISED :
		-	T. RAMMACHER 02-02-99
	PLOT DATE = 5/14/2014	DATE :	REVISED :
		-	C. JUCIUS 01-31-07

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ARTERIAL ROAD
INFORMATION SIGN

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2706	1A&BYRS-2	LAKE	28	27
TC-22			CONTRACT NO. 60V04	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				