

MATCH LINE STA. 120+00

MATCH LINE STA. 135+00

PROP. THPL. PVMT. MARKING -4"  
DOUBLE CENTERLINE, YELLOW (TYP.)

IL. RTE. 64



PROP. THPL. PVMT. MARKING -4"  
YELLOW, 10' LINE, 30' SPACING (TYP.)

PROP. THPL. PVMT. MARKING -4"  
EDGE LINE, WHITE (TYP.)

120+00

125+00

130+00

PROP. HMA SURFACE REMOVAL, 2 1/4"  
PROP. POLY. LEVELING BINDER (MM), IL-4.75, N50, 3/4"  
PROP. HMA SURFACE COURSE, MIX "D", N70, 1 1/2"

MATCH LINE STA. 135+00

MATCH LINE STA. 150+00

IL. RTE. 64



PROP. THPL. PVMT. MARKING -4"  
YELLOW, 10' LINE, 30' SPACING (TYP.)

135+00

140+00

145+00

PROP. HMA SURFACE REMOVAL, 2 1/4"  
PROP. POLY. LEVELING BINDER (MM), IL-4.75, N50, 3/4"  
PROP. HMA SURFACE COURSE, MIX "D", N70, 1 1/2"

PROP. THPL. PVMT. MARKING -4"  
EDGE LINE, WHITE (TYP.)

① EXIST. TERMINAL SECTION TO BE REPLACED WITH NEW TYPE 1 (SPECIAL) -  
TANGENT 50 FT LONG. SEE STANDARD 630301 - DISTRICT DETAIL (BD-34).

OTHER PAY ITEMS WITH QUANTITIES ESTIMATED FOR THIS AREA INCLUDE:

- REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
- FURNISHED EXCAVATION
- TOPSOIL FURNISH AND PLACE, 4"
- SEEDING, CLASS 2A
- NITROGEN FERTILIZER NUTRIENT
- PHOSPHEROUS FERTILIZER NUTRIENT
- POTASSIUM FERTILIZER NUTRIENT
- EROSION CONTROL BLANKET
- AGGREGATE SHOULDER, TYPE B - 10"
- GUARDRAIL REMOVAL

FILE NAME =	USER NAME = pyzzenowskirb	DESIGNED -	REVISED -
ca:\pwr_work\p1dot\pyzzenowskirb\d031229\0151412-sht-plan.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 5/21/2014	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 64 (COUNTY LINE RD TO IL 47)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	126RS-5	KANE	22	9
CONTRACT NO. 60V07				
ILLINOIS FED. AID PROJECT				