



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 18, 2014

SUBJECT: FAP Route 303 (US14/IL173)
Section (21X,29V & 132) RS-2
McHenry County
Contract No. 60V12
Item No. 25, August 1, 2014 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions.
2. Revised page 2 of the Special Provisions.
3. Revised sheet 2 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger" followed by "P.E." in a smaller font.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: John Fortmann, Region 1, District 1, Tim Kell; Estimates

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT	1
DESCRIPTION OF IMPROVEMENT	1
MAINTENANCE OF ROADWAYS	1
CLEANING EXISTING DRAINAGE STRUCTURES	2
TRAFFIC CONTROL PLAN	2
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1)	3
HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER	5
FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1)	6
FRICTION SURFACE AGGREGATE (D1)	6
GRADING AND SHAPING SHOULDERS	9
GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1)	9
HOT-MIX ASPHALT – PRIME COAT (D-1)	10
HOT MIX ASPHALT MIXTURE IL-4.75 (DIST 1)	14
HMA MIXTURE DESIGN REQUIREMENTS (D-1)	15
HOT MIX ASPHALT QUALITY CONTROL FOR PERFORMANCE (BMPR)	20
PUBLIC CONVENIENCE AND SAFETY (DIST 1)	26
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (D-1)	27
RECLAIMED WATER (D-1)	37
STATUS OF UTILITIES TO BE ADJUSTED	38
TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR INSTALLATION ON ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS.	39
TEMPORARY INFORMATION SIGNING	42
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	44
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	48
CONCRETE GUTTER, CURB, MEDIAN, AND PAVED DITCH (BDE)	49
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	50
CONTRACT CLAIMS (BDE)	52
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	53
PAVEMENT PATCHING (BDE)	62
PAYROLLS AND PAYROLL RECORDS (BDE)	62
PORTLAND CEMENT CONCRETE EQUIPMENT (BDE)	64

Revised 7/17/14

PROGRESS PAYMENTS (BDE) 64
QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE)..... 65
REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE)..... 65
TRACKING THE USE OF PESTICIDES (BDE)..... 66
WARM MIX ASPHALT (BDE) 66
WEEKLY DBE TRUCKING REPORTS (BDE)..... 70
WORKING DAYS (BDE)..... 70
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)..... 71
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)..... 74
PROJECT LABOR AGREEMENT - QUARTERLY EMPLOYMENT REPORT 78
PROJECT LABOR AGREEMENT 79

Revised 7/14/14

CLEANING EXISTING DRAINAGE STRUCTURES

Effective: September 30, 1985

Revised: December 1, 2011

All existing storm sewers, pipe culverts, manholes, catch basins and inlets shall be considered as drainage structures insofar as the interpretation of this Special Provision is concerned. When specified for payment, the location of drainage structures to be cleaned will be shown on the plans.

All existing drainage structures which are to be adjusted or reconstructed shall be cleaned according to Article 602.15 of the Standard Specifications. This work will be paid for according to accordance with Article 602.16 of the Standard Specifications.

All other existing drainage structures which are specified to be cleaned on the plans will be cleaned according to Article 602.15 of the Standard Specifications.

Basis of Payment. This work will be paid for at the contract unit price each for DRAINAGE STRUCTURES TO BE CLEANED, and at the contract unit price per foot (meter) for STORM SEWERS TO BE CLEANED, of the diameter specified.

TRAFFIC CONTROL PLAN

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS:

701101, 701301, 701306, 701311, 701336, 701501, 701502, 701701, 701801, & 701901

Revised 7/18/14