

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 KANE COUNTY	0005 KENDALL COUNTY					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 KANE COUNTY	0005 KENDALL COUNTY				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	19	13	6					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.7	0.3				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	714	500	214					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.7	0.3				
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.7	0.3					70300100	SHORT TERM PAVEMENT MARKING	FOOT	1632	1142	490				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	91	64	27					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	93.6	36.4	57.2				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1427	1000	427					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11960	8372	3588				
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	12973	9081	3892					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	167	117	50				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	160	112	48					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	90	63	27				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	64	45	19					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	49	21				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	200	140	60					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	93.6	36.4	57.2				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2.8	1.2					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11960	8372	3588				
67100100	MOBILIZATION	L SUM	1	0.7	0.3					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	167	117	50				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1		1					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	90	63	27				
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.7	0.3														

*Specialty Items

FILE NAME =	USER NAME = gulliametp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwr\mrt\pwr\gulliametp\p00312333\0152612-01-01.dgn		DRAWN -	REVISED -		360	16RS-5	KANE/KENDALL	19	3				
PLOT SCALE = 1000000' / 1"		CHECKED -	REVISED -						CONTRACT NO. 60V19				
PLOT DATE = 5/30/2014		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		