

EARTHWORK SCHEDULE

STAGE 1						STAGE 2					FINAL					
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)	UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)	* UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%)	UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	* TOPSOIL EXCAVATION AND PLACEMENT
STA. 95+00 TO 96+00	18.15	15.43	0.00	0.00	15.43	24.26	20.62	0.00	0.00	20.62	0.00	0.00	0.00	0.00	0.00	42.00
STA. 96+00 TO 97+00	30.37	25.81	0.00	0.00	25.81	55.56	47.22	0.00	4.63	42.59	31.30	26.60	0.00	3.89	22.71	51.00
STA. 97+00 TO 97+23.12	5.74	4.88	0.00	0.00	4.88	16.36	13.90	0.00	1.07	12.83	20.12	17.10	0.00	0.90	16.21	0.00
STA. 97+23.13 TO 98+00	22.35	19.00	0.00	0.00	19.00	66.34	56.39	0.00	2.14	54.26	101.08	85.92	0.00	5.98	79.94	0.00
STA. 98+00 TO 98+59.04	21.32	18.12	0.00	3.56	14.56	62.32	52.97	0.00	2.84	50.13	101.35	86.15	0.00	12.57	73.58	0.00
STA. 98+59.04 TO 99+00	19.80	16.83	0.00	2.73	14.09	43.08	36.62	0.00	1.14	35.48	47.41	40.30	0.00	13.73	26.57	0.00
STA. 99+00 TO 99+97.06	27.86	23.68	0.00	0.00	23.68	45.11	38.35	110.00	0.72	37.63	19.23	16.35	0.00	19.41	-3.06	0.00
STA. 99+97.06 TO 100+00	3.01	2.55	0.00	0.00	2.55	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
STA. 100+00 TO 101+00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
STA. 101+00 TO 102+00	27.04	22.98	0.00	0.00	22.98	55.19	46.91	0.00	86.67	-39.76	150.19	127.66	0.00	0.00	127.66	0.00
STA. 102+00 TO 103+00	11.30	9.60	0.00	14.81	-5.21	47.96	40.77	0.00	16.67	24.10	57.59	48.95	0.00	0.00	48.95	0.00
STA. 103+00 TO 104+00	17.22	14.64	0.00	14.81	-0.18	34.26	29.12	0.00	1.48	27.64	33.15	28.18	0.00	0.00	28.18	0.00
STA. 104+00 TO 105+00	7.04	5.98	0.00	0.00	5.98	12.22	10.39	0.00	0.00	10.39	22.22	18.89	0.00	0.00	18.89	0.00
TOTAL	211.19	179.51	0.00	35.92	143.59	462.66	393.26	110.00	117.35	275.91	583.64	496.10	0.00	56.48	439.61	93.00

* UNSUITABLE MATERIAL SHALL BE USED AS TOPSOIL WITHIN THE PROJECT LIMITS.
THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD
FOR TOPSOIL EXCAVATION AND PLACEMENT.

FILE NAME = P:\2011\ME11007_Ver-Var-PhI\CADD\W006_US14_Shts\33A-D160\25-ear-thworkSCH.dgn
 PLOT SCALE = 2.0000' = 1" = 100'
 USER NAME = Millennium Professional Services



2600 Warrenville Road, Suite 203, Downers Grove, IL 60515
 630.705.0110 voice, 630.839.2566 fax
 www.mps-ill.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - TVN/MG	REVISED -
DRAWN - MG/JP	REVISED -
CHECKED - TVN	REVISED -
DATE - 6/19/2014	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US ROUTE 14 OVER LAWRENCE CREEK TRIBUTARY
EARTHWORK SCHEDULE**

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
066	21B-R	MCHENRY	40	33A
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60V25	

P:\2011\ME11007_Ver-Var-PhI\CADD\W006_US14_Shts\33A-D160\25-ear-thworkSCH.dgn