

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	0005									
20400800	FURNISHED EXCAVATION	CU YD	13	13								
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	6	6								
25000210	SEEDING, CLASS 2A	ACRE	0.01	0.01								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1								
25100630	EROSION CONTROL BLANKET	SO YD	40	40								
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49	49								
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1296	1296								
40600895	CONSTRUCTING TEST STRIP	EACH	1	1								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	460	460								
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3185	3185								
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	32175	32175								
44003510	MEDIAN REMOVAL, PARTIAL DEPTH	SQ FT	920	920								
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	500	500								
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	500	500								
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	600	600								

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE 0005				
CODE NO	ITEM	UNIT	0005									
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SO YD	25	25								
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	476	476								
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1								
63200310	GUARDRAIL REMOVAL	FOOT	50	50								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3								
67100100	MOBILIZATION	L SUM	1	1								
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1								
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1								
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1								
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9630	9630								
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	233	233								
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29600	29600								
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	245	245								
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	120	120								

\*Specialty Items

FILE NAME	USER NAME	DESIGNED	REVISIONS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 6 / EAMES ST. (0.2 MI. S. OF MCCLINTOCK RD. TO I-55) SUMMARY OF QUANTITIES	F.A.P. DIST. 856	SECTION IERB, JRRS-4	COUNTY WILL	TOTAL SHEETS 21	SHEET NO. 3	CONTRACT NO. 60V44
DATE	DATE	CHECKED	REVISIONS	SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			