SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4221	4221					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1362	1362					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	135	135					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	163	163					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	71	71					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	151	151					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	956	956					
	X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	6961	6961					
	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	250	250					
	X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	150	150					
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22					
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	225	225					
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	23	23					
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	179.9	179.9					
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	10	10					
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1					

* Specialty Items

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

Rev.

FILE NAME = c:\pw_work\dot\hardmeier\d0315416\D157212-sht-plan.dgn	USER NAME = hardmeier	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/23/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 2 OF 2 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
333	14RS-7	MCHENRY	22	4

CONTRACT NO. 60V48

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT