			URBAN	ROADWAY	FIBER OPTIC CONDUIT 100% MCHENRY COUNTY	TRAFFIC SIGNALS					MULTI-USE PATH	WATER MAIN AND SANITARY SEWER	
						US RTE 14 & DOTY ROAD 93.3% STATE 6.7% WOODSTOCK	US RTE 14 & W LAKE SHORE DR 95% STATE 5% WOODSTOCK	EMERGENCY VEHICLE PREEMPTION 100% WOODSTOCK	INTERCONNECT 100% STATE	US RTE 14 & LAKE SHORE DR 90% STATE 10% WOODSTOCK	80% STATE 20% MCCD	100% WOODSTOCK	100% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY 100% STATE	100% STATE		CONSTRUCTION CODE							
				0003	0021	0021	0021	0021	0021	0021	0028	0043	0043
40701846	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/4"	SQ YD	1,006	1,006									
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	1,378	1,378									
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	109,098	109,098									
42001300	PROTECTIVE COAT	SQ YD	150,798	150,798									
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1,752								1,752		
42400800	DETECTABLE WARNINGS	SQ FT	296								296		
44000100	PAVEMENT REMOVAL	SQ YD	104,015	104,015									
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1,669	1,669									
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	36,291	36,291									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,860	1,860									
44000300	CURB REMOVAL	FOOT	94	94									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6,270	6,270									
44003100	MEDIAN REMOVAL	SQ FT	141	141									
44004000	PAVED DITCH REMOVAL	FOOT	133	133									
44004250	PAVED SHOULDER REMOVAL	SQ YD	13,588	13,588									

15

* SPECIALTY ITEM

FILE NAME = C:\Projects\US14LSD-LucasRd-LongTran\MicroStation Design Files\Sheets\SUDDBNW.DGN	USER NAME = BBuser88	DESIGNED -	REVISED -
		DRAWN - AMB	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED - BRH	REVISED -
exp U.S. Services Inc. Chicago, IL BUILDINGS-EARTH & ENVIRONMENT-ENERGY INDUSTRIAL-INFRASTRUCTURE-SUSTAINABILITY	PLOT DATE = 6/18/2014	DATE - 11/01/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
U.S. ROUTE 14

SUMMARY OF QUANTITIES - 1

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	4C
		CONTRACT NO. 62268		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		