

CODE NO.	ITEM	UNIT	URBAN		TRAFFIC SIGNALS							MULTI-USE PATH		WATER MAIN AND SANITARY SEWER	
			TOTAL QUANTITY	100% STATE	ROADWAY 100% STATE	FIBER OPTIC CONDUIT 100% MCHENRY COUNTY	US RTE 14 & DOTY ROAD 93.3% STATE 6.7% WOODSTOCK	US RTE 14 & LAKE SHORE DR 95% STATE 5% WOODSTOCK	EMERGENCY VEHICLE PREEMPTION 100% WOODSTOCK	INTERCONNECT 100% STATE	US RTE 14 & LAKE SHORE DR 90% STATE 10% WOODSTOCK	80% STATE 20% MCCD	100% WOODSTOCK	100% STATE	
			100% STATE	CONSTRUCTION CODE	0003	0021	0021	0021	0021	0021	0021	0028	0043	0043	
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SO YD	15										15		
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SO YD	131	102										29	
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SO YD	290	290											
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	640	640											
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	144	144											
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	78	78											
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,494	1,494											
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	2,563	2,563											
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SO YD	449	449											
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	236	236											
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	1,341	1,341											
48300415	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	SO YD	19,911	19,911											
50105220	PIPE CULVERT REMOVAL	FOOT	1,679	1,679											
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	13	13											
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	18	18											

\* SPECIALTY ITEM

C:\Projects\US14\LSO-LucasRd-LongTran\Station Design Files\Sheet\SU0008HW.DGN  
 exp U.S. Services Inc.  
 CHICAGO, IL  
 EXP  
 DESIGN, EARTH & ENVIRONMENT, ENERGY  
 INDUSTRIAL INFRASTRUCTURE, SUSTAINABILITY

FILE NAME :	USER NAME : **user**	DESIGNED -	REVISED -
C:\Projects\US14\LSO-LucasRd-LongTran\Station Design Files\Sheet\SU0008HW.DGN	DRAWN - AMB	REVISIONS	
exp U.S. Services Inc.	CHECKED - BRH	DATE - 11/01/13	REVISED -
CHICAGO, IL	PLOT SCALE * 100.0000 "/ in.		
EXP	PLOT DATE * 6/19/2014		

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**  
 U.S. ROUTE 14

SUMMARY OF QUANTITIES - I			
SCALE: N.T.S.	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	40
CONTRACT NO. 62268			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	