URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY 100% STATE	ROADWAY 100% STATE	FIBER OPTIC CONDUIT 100% MCHENRY COUNTY	TRAFFIC SIGNALS: US RTE 14 & DOTY ROAD 93.3% STATE 6.7% WOODSTOCK	TRAFFIC SIGNALS: US RTE 14 & W LAKE SHORE DR 95% STATE 5% WOODSTOCK	TRAFFIC SIGNALS: EMERGENCY VEHICLE PREEMPTION 100% WOODSTOCK	TRAFFIC SIGNALS: INTERCONNECT 100% STATE	TRAFFIC SIGNALS: US RTE 14 & LAKE SHORE DR 90% STATE 10% WOODSTOCK	MULTI-USE PATH 80% STATE 20% MCCD	WATER MAIN AND SANITARY SEWER 100% WOODSTOCK	WATER MAIN AND SANITARY SEWER 100% STATE
				CONSTRUCTION CODE									
			100% STATE	0003	0021	0021	0021	0021	0021	0021	0028	0043	0043
X0327769	INSERTION VALVES 10"	EACH	2									2	
56400100	FIRE HYDRANTS TO BE MOVED	EACH	5									3	2
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	4									2	2
56400800	FIRE HYDRANT AND VALVE TO BE MOVED	EACH	7									4	3
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	12	12									
60107600	PIPE UNDERDRAINS 4"	FOOT	5,121	5,121									
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	284	284									
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	7	7									
60200205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4									
60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	22	22									
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	14	14									
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	147	147									
60203905	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2									
60204005	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1									
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3									

* SPECIALTY ITEM

FILE NAME = C:\Projects\US14LSO-LucasRd-LongTran\MicroStation Design Files\Sheet\SU00B8NW.DGN	USER NAME = BBuser88	DESIGNED -	REVISED -
		DRAWN - AMB	REVISED -
exp U.S. Services Inc. Chicago IL BUILDINGS-EARTH & ENVIRONMENT-ENERGY INDUSTRIAL-INFRASTRUCTURE-SUSTAINABILITY	PLOT SCALE = 100.0000 ' / in.	CHECKED - BRH	REVISED -
	PLOT DATE = 6/10/2014	DATE - 11/01/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
U.S. ROUTE 14

SUMMARY OF QUANTITIES - 1

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	40
		CONTRACT NO. 62268		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		