

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		CONSTRUCTION CODE											
			100% STATE		TRAFFIC SIGNALS											
			100% STATE	URBAN	ROADWAY	FIBER OPTIC CONDUIT 100% MCHENRY COUNTY	US RTE 14 & DOTY ROAD 93.3% STATE 6.7% WOODSTOCK	US RTE 14 & LAKE SHORE DR 95% STATE 5% WOODSTOCK	EMERGENCY VEHICLE PREEMPTION 100% WOODSTOCK	INTERCONNECT 100% STATE	US RTE 14 & LAKE SHORE DR 90% STATE 10% WOODSTOCK	MULTI-USE PATH 80% STATE 20% MCHENRY	WATER MAIN AND SANITARY SEWER			
0003	0021	0003	0021	0021	0021	0021	0021	0021	0021	0028	0043	0043				
X5630010	CUT AND CAP EXISTING 10" WATER MAIN	EACH	3												3	
X5630012	CUT AND CAP EXISTING 12" WATER MAIN	EACH	1													1
X5630708	CONNECTION TO EXISTING WATER MAIN 8"	EACH	3												1	2
X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	8	8												
X6061100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	SO FT	17,397	17,397												
X6061815	COMBINATION CONCRETE CURB AND GUTTER, TYPE M (SPECIAL)	FOOT	95	95												
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	1,056	1,056												
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	18	18												
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1												
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SO FT	873	873												
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	120,324	120,324												
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	2,689	2,689												
X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	606	606												
X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	641	641												
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	595	595												

* SPECIALTY ITEM

C:\Projects\US14150-LucasRd-LongTran\AutoStation Design Files\Sheet\SU000.RD.DGN
 exp U.S. Services Inc.
 11/01/13
 6/18/2014

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
C:\Projects\US14150-LucasRd-LongTran\AutoStation Design Files\Sheet\SU000.RD.DGN	exp U.S. Services Inc.	DRAWN - AMB	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED - BRH	REVISED -
	PLOT DATE = 6/18/2014	DATE - 11/01/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
 U.S. ROUTE 14

SUMMARY OF QUANTITIES - VIII			
SCALE: N.T.S.	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	11
CONTRACT NO. 62268				
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				