

X6640300 CHAIN LINK FENCE REMOVAL				TOTAL 1,056 FOOT
LOCATION	FROM STATION	TO STATION	OFFSET	SUBTOTALS
US RTE 14	430+17	432+50	RT	231
US RTE 14	432+50	438+02	RT	551
US RTE 14	461+24	462+78	RT	274

X7830050 RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL					TOTAL 24 EACH
LOCATION	FROM STATION	TO STATION	AVERAGE SPACING	SUBTOTALS	
US RTE 14	156+00	165+40	80	24	

Z0073345 SLEEPER SLAB		TOTAL 205 FOOT
LOCATION		SUBTOTALS
US RTE 14 & LAKE SHORE DR (S)		95
US RTE 14 & LAKE SHORE DR (N)		109.81

Z0062456 TEMPORARY PAVEMENT						TOTAL 39,739 SQ YD
LOCATION	FROM STATION	TO STATION	OFFSET	AREA (SQ FT)	SUBTOTALS	
PRE-STAGE						
US RTE 14	165+76	168+53	RT	1608.93	178.8	
US RTE 14	325+17	325+57	LT	877.45	97.5	
US RTE 14	325+21	334+00	RT	7643.17	849.2	
US RTE 14	334+00	348+00	RT	15425.66	1714.0	
US RTE 14	348+00	362+00	RT	25900.30	2877.8	
US RTE 14	362+00	365+38	RT	7498.47	833.2	
US RTE 14	365+79	376+00	RT	24753.51	2750.4	
LAKE SHORE DR	45+67	47+25	RT	1283.57	142.6	
US RTE 14	376+00	383+04	RT/LT	7510.69	834.5	
US RTE 14	379+70	390+00	LT	18256.99	2028.6	
US RTE 14	390+00	404+00	LT	20647.78	2294.2	
DOTY ROAD	0+16	1+50	LT	2441.62	271.3	
US RTE 14	404+00	418+00	LT	36284.72	4031.6	
US RTE 14	418+00	431+12	LT	32219.81	3580.0	
US RTE 14	440+20	446+00	LT	7908.56	878.7	
US RTE 14	446+00	460+00	LT	24956.44	2772.9	
US RTE 14	460+00	465+65	LT	9568.85	1063.2	
US RTE 14	466+68	474+00	LT	12699.07	1411.0	
US RTE 14	474+00	488+00	LT	24406.25	2711.8	
US RTE 14	488+00	489+72	LT	1684.48	187.2	
US RTE 14	488+00	493+00	RT	9728.68	1081.0	
LAKE SHORE DR	47+25	488+59	RT	888.68	98.7	
LAKE SHORE DR	42+48	43+00	RT	182.73	20.3	
DOTY ROAD	1+50	3+05	LT	1614.66	179.4	
STAGE 1.1						
US 14	331+83	334+75	LT	1651.87	183.5	
US 14	352+80	355+60	LT/RT	4009.4	445.5	
US 14	362+10	365+41	LT	3906.97	434.1	
US 14	377+50	379+70	LT	5435.38	603.9	
US 14	396+71	397+42	LT/RT	1103.57	122.6	
US 14	430+45	432+50	LT/RT	3322.43	369.2	
US 14	432+50	432+78	LT/RT	216.11	24.0	
US 14	485+00	488+00	RT	6756.51	750.7	
STAGE 1.1 A-3						
US RTE 14	325+74	335+00	LT/RT	9855.90	1095.1	
STAGE 1.1 C-2						
US RTE 14	397+42	397+66	LT/RT	251.23	27.9	
STAGE 1.2						
US RTE 14	369+07	373+53	LT/RT	4287.41	476.4	
US RTE 14	478+67	483+14	LT	4287.44	476.4	
STAGE 2.1						
US RTE 14	429+18	431+34	LT/RT	2392.34	265.8	
US RTE 14	466+09	468+63	LT/RT	3179.86	353.3	
STAGE 2.1 A-1						
LILY POND RD	302+12	306+53		4545.62	505.1	
STAGE 2.1 B-1						
RIDGEFIELD RD	432+47	407+61		6455.00	717.2	

T:\DOCUMENT\1934\9901\CIVIL\DCN\SC000\FZ.DGN
 11-07-2013 16:19:03
 HECHTBR

FILE NAME =	USER NAME = HECHTBR	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION U.S. ROUTE 14	SCHEDULE OF QUANTITIES - VIII			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL		DRAWN - BRH	REVISED -					305	27R-2	MCHENRY	673	35
exp U.S. Services Inc. Chicago, IL BUILDINGS-EARTH & ENVIRONMENT-ENERGY INDUSTRIAL-INFRASTRUCTURE-SUSTAINABILITY	PLOT SCALE = *SCALE*	CHECKED - TMH	REVISED -		SCALE: N.T.S.	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 62268		
	PLOT DATE = *DATE*	DATE - 11/01/13	REVISED -					FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				