

PROPOSED SIGN SCHEDULE

SIGN I.D.	ROAD	PROP STA	PROP OFFSET	SIGN DESCRIPTION	GROUND MOUNTING TYPE	TYPE/I.D.	DIMENSIONS		AREA	72000105	72800100	73000100	X7280105
							HEIGHT	WIDTH	SF	SIGN PANEL TYPE 1	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)
							FT	FT	SF	SF	FT	FT	FT
S-201	US ROUTE 14	327+85	11' R	LEFT TURN ONLY	TELESCOPING	R3-5L	2.50	2.00	5.00	5.00	13.5		
S-202	US ROUTE 14	328+50	62' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	18.5		
S-203	US ROUTE 14	346+00	55' R	UNLAWFUL TO PASS SCHOOL BUS	TELESCOPING	S4-1104	2.50	2.50	6.25	6.25	18.0		
S-204	US ROUTE 14	348+00	53' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	18.0		
S-205	US ROUTE 14	351+50	8' R	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	13.5		
S-205A				LEFT TURN ONLY		R3-5L	2.50	2.00	5.00	5.00			
S-206	US ROUTE 14	353+55	8' R	LEFT TURN ONLY	TELESCOPING	R3-5L	2.50	2.00	5.00	5.00	13.5		
S-207	US ROUTE 14	357+50	52' R	SIGNAL AHEAD	TELESCOPING	W3-3	2.50	2.50	6.25	6.25	18.0		
S-207A				LAKE SHORE DRIVE		CUSTOM	0.67	3.00	2.01	2.01			
S-208	US ROUTE 14	328+50	10' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	14.0		
S-209	US ROUTE 14	364+93	8' L	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	13.5		
S-209A				LEFT TURN ONLY		R3-5L	2.50	2.00	5.00	5.00			
S-210	US ROUTE 14	364+30	57' R	RIGHT TURN ONLY	TELESCOPING	R3-5R	3.00	2.50	7.50	7.50	16.0		
S-211	LAKE SHORE DRIVE	44+62	36' R	US ROUTE 14	TELESCOPING	M1-4	2.00	2.00	4.00	4.00	16.5		
S-211A				TWO DIRECTIONAL ARROW		M6-4	1.25	1.75	2.19	2.19			
S-212	US ROUTE 14	366+15	8' R	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	13.5		
S-212A				LEFT TURN ONLY		R3-5L	2.50	2.00	5.00	5.00			
S-215	US ROUTE 14	373+10	53' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	15.5		
S-217	US ROUTE 14	380+00	56' R	CURVE SIGN (LEFT)	WOOD POST	W1-2L	3.00	3.00	9.00	9.00		19.0	
S-218	US ROUTE 14	387+20	53' R	NO RIGHT TURN	TELESCOPING	R3-1	3.00	3.00	9.00	9.00	18.0		
S-218A				EXCEPT AUTHORIZED VEHICLES		R3-1101	2.00	3.00	6.00	6.00			
S-219	US ROUTE 14	388+85	51' R	HOSPITAL	TELESCOPING	D9-2	2.00	2.00	4.00	4.00	16.0		
S-219A				DIRECTIONAL ARROW (UP)		M6-3	1.25	1.75	2.19	2.19			
S-220	US ROUTE 14	390+05	51' R	SIGNAL AHEAD	TELESCOPING	W3-3	2.50	2.50	6.25	6.25	17.5		
S-220A				DOTY ROAD		CUSTOM	0.67	2.00	1.34	1.34			
S-221	US ROUTE 14	394+10	53' R	HOSPITAL	TELESCOPING	D9-2	2.00	2.00	4.00	4.00	16.0		
S-221A				DIRECTIONAL ARROW (RIGHT)		M6-1	1.25	1.75	2.19	2.19			
S-223	US ROUTE 14	396+45	54' R	RIGHT TURN ONLY	TELESCOPING	R3-5R	3.00	2.50	7.50	7.50	16.0		
S-224	US ROUTE 14	396+75	8' L	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	14.0		
S-224A				U TURN ONLY		CUSTOM	3.00	2.50	7.50	7.50			
S-225	DOTY ROAD	0+77	28' L	US ROUTE 14	SIGNAL POST	M1-4	2.00	2.00	4.00	4.00			
S-225A				TWO DIRECTIONAL ARROW		M6-4	1.25	1.75	2.19	2.19			
S-226	US ROUTE 14	397+99	8' R	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	13.5		
S-226A				LEFT TURN ONLY		R3-5L	2.50	2.00	5.00	5.00			
S-227	US ROUTE 14	399+50	54' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	17.0		
S-228	US ROUTE 14	403+70	54' R	US ROUTE 14	TELESCOPING	M1-4	2.00	2.00	4.00	4.00	18.5		
S-228A				EAST		M3-2	1.00	2.00	2.00	2.00			
S-229	US ROUTE 14	413+50	55' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	18.5		
S-230	US ROUTE 14	422+35	56' R	CURVE AND INTERSECTION	WOOD POST	W1-10R	3.00	3.00	9.00	9.00		17.0	
S-231	US ROUTE 14	424+90	55' R	SIDE STREET (LEFT)	TELESCOPING	W2-2L	2.50	2.50	6.25	6.25	18.0		
S-231A				LILY POND ROAD		CUSTOM	0.67	3.00	2.01	2.01			
S-232	US ROUTE 14	427+11	8' L	LEFT TURN ONLY	TELESCOPING	R3-5L	2.50	2.00	5.00	5.00	13.5		
S-233	US ROUTE 14	430+10	8' L	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	13.5		
S-233A				LEFT TURN ONLY		R3-5L	2.50	2.00	5.00	5.00			
S-234	US ROUTE 14	430+55	53' R	TWO DIRECTIONAL LARGE ARROW	WOOD POST	W1-7	2.00	4.00	8.00	8.00		14.0	
S-235	US ROUTE 14	431+07	8' R	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	14.0		
S-235A				U TURN ONLY		CUSTOM	3.00	2.50	7.50	7.50			

T:\DOCUMENTS\1934\9901\CIVIL\DCN\SCN00\_18.DGN  
 exp U.S. Services Inc.  
 11-07-2013 16:32:00  
 HECHTBR

FILE NAME =  
 \*FILEL\*  

 exp U.S. Services Inc.  
 CHICAGO, IL  
 BUILDINGS-EARTH & ENVIRONMENT-ENERGY  
 INDUSTRIAL-INFRASTRUCTURE-SUSTAINABILITY

USER NAME = HECHTBR	DESIGNED -	REVISED -
PLOT SCALE = *SCALE*	CHECKED - BRH	REVISED -
PLOT DATE = *DATE*	DATE - 11/01/13	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**  
 U.S. ROUTE 14

<b>PROPOSED SIGN SCHEDULE - I</b>			
SCALE: N.T.S.	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	390
CONTRACT NO. 62268				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				