

PROPOSED SIGN SCHEDULE

SIGN I.D.	ROAD	PROP STA	PROP OFFSET	SIGN DESCRIPTION	GROUND MOUNTING TYPE	TYPE/I.D.	DIMENSIONS		AREA	72000105	72800100	73000100	X7280105
							HEIGHT	WIDTH	SF	SIGN PANEL TYPE 1	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)
							FT	FT	SF	SF	FT	FT	FT
S-236	US ROUTE 14	434+09	8' R	U TURN ONLY	TELESCOPING	CUSTOM	3.00	2.50	7.50	7.50	14.0		
S-238	US ROUTE 14	436+50	41' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	16.0		
S-239	US ROUTE 14	448+90	8' L	U TURN ONLY	TELESCOPING	CUSTOM	3.00	2.50	7.50	7.50	14.0		
S-240	US ROUTE 14	451+67	8' R	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	14.0		
S-240A				U TURN ONLY		CUSTOM	3.00	2.50	7.50	7.50			
S-242	US ROUTE 14	459+70	41' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	15.5		
S-245	US ROUTE 14	467+60	53' R	TWO DIRECTIONAL LARGE ARROW	WOOD POST	W1-7	2.00	4.00	8.00	8.00		14.0	
S-246	US ROUTE 14	468+15	8' R	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	14.0		
S-246A				U TURN ONLY		CUSTOM	3.00	2.50	7.50	7.50			
S-248	US ROUTE 14	478+50	46' R	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	16.0		
S-249	US ROUTE 14	489+50	41' R	INTERSECTION WARNING SIGN	TELESCOPING	W2-1	2.50	2.50	6.25	6.25	17.5		
S-249A				COLLEGE ENT (LEFT)/ LUCAS RD (RIGHT)		CUSTOM	1.25	3.00	3.75	3.75			
S-250	US ROUTE 14	479+00	57' L	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	16.5		
S-251	US ROUTE 14	469+87	49' R	EAST	TELESCOPING	M3-2	1.00	2.00	2.00	2.00	15.5		
S-251A				US ROUTE 14		M1-4	2.00	2.00	4.00	4.00			
S-254	RIDGEFIELD ROAD	850+78	32' L	STOP SIGN	WOOD POST	R1-1	3.00	3.00	9.00	9.00		17.0	
S-255	RIDGEFIELD ROAD	850+78	36' L	US ROUTE 14	TELESCOPING	M1-4	2.00	2.00	4.00	4.00			17.0
S-255A				TWO DIRECTIONAL ARROW		M6-4	1.25	1.75	2.19	2.19			
S-256	US ROUTE 14	467+20	8' L	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	13.5		
S-256A				LEFT TURN ONLY		R3-5L	2.50	2.00	5.00	5.00			
S-258	US ROUTE 14	463+00	57' L	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	16.5		
S-259	US ROUTE 14	453+75	8' R	U TURN ONLY	TELESCOPING	CUSTOM	3.00	2.50	7.50	7.50	14.0		
S-260	US ROUTE 14	450+98	8' L	KEEP RIGHT	TELESCOPING	R4-7	2.50	2.00	5.00	5.00	14.0		
S-260A				U TURN ONLY		CUSTOM	3.00	2.50	7.50	7.50			
S-262	US ROUTE 14	446+05	58' L	INTERSECTION ON CURVE WARNING	WOOD POST	W1-10L	3.00	3.00	9.00	9.00		17.0	
S-263	US ROUTE 14	439+00	58' L	SIDE STREET (LEFT)	TELESCOPING	W2-2L	2.50	2.50	6.25	6.25	18.0		
S-263A				LILY POND ROAD		CUSTOM	0.67	3.00	2.01	2.01			
S-264	US ROUTE 14	465+49	62' L	WEST	TELESCOPING	M3-4	1.00	2.00	2.00	2.00	16.0		
S-264A				US ROUTE 14		M1-4	2.00	2.00	4.00	4.00			
S-265	US ROUTE 14	431+35	69' L	RIGHT TURN ONLY	TELESCOPING	R3-5R	3.00	2.50	7.50	7.50	15.5		
S-266	LILY POND ROAD	800+72	36' L	STOP SIGN	WOOD POST	R1-1	3.00	3.00	9.00	9.00		16.0	
S-267	LILY POND ROAD	800+72	41' L	US ROUTE 14	TELESCOPING	M1-4	2.50	2.00	5.00	5.00	19.0		
S-267A				TWO DIRECTIONAL ARROW		M6-4	1.25	1.75	2.19	2.19			
S-268	US ROUTE 14	426+25	53' L	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	18.0		
S-269	US ROUTE 14	434+04	67' L	RIGHT TURN ONLY	TELESCOPING	R3-5R	3.00	2.50	7.50	7.50	16.0		
S-270	US ROUTE 14	420+00	53' L	UNLAWFUL TO PASS SCHOOL BUS	TELESCOPING	S4-1104	2.50	2.50	6.25	6.25	17.5		
S-271	US ROUTE 14	408+00	53' L	SIGNAL AHEAD	TELESCOPING	W3-3	2.50	2.50	6.25	6.25	19.5		
S-271A				DOTY ROAD		CUSTOM	0.67	2.00	1.34	1.34			
S-272	US ROUTE 14	406+00	53' L	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	18.0		
S-273	US ROUTE 14	401+85	51' L	HOSPITAL	TELESCOPING	D9-2	2.00	2.00	4.00	4.00	16.5		
S-273A				DIRECTIONAL ARROW (LEFT)		M6-1	1.25	1.75	2.19	2.19			
S-274	DRIVEWAY EXIT	399+52	70' L	RIGHT TURN ONLY	TELESCOPING	R3-5R	3.00	2.50	7.50	7.50	17.0		
S-275	US ROUTE 14	445+00	57' L	SPEED LIMIT 45	TELESCOPING	R2-1	3.00	2.50	7.50	7.50	16.5		
S-276	US ROUTE 14	397+35	70' L	TWO DIRECTIONAL LARGE ARROW	WOOD POST	W1-7	2.00	4.00	8.00	8.00		14.0	
S-277	US ROUTE 14	394+80	55' L	CURVE AHEAD (RIGHT)	WOOD POST	W1-2R	3.00	3.00	9.00	9.00		17.5	
S-278	US ROUTE 14	391+80	67' L	US ROUTE 14	TELESCOPING	M1-4	2.50	2.00	5.00	5.00	18.5		
S-278A				WEST		M3-4	2.00	1.00	2.00	2.00			

I:\SGN00\14.DGN...TT18006.LJ.DGN...SGN00_14.DGN...HECHTBR T:\DOCUMENT\1934\9901\CIVIL\DGN\SGN00_19.DGN
 11-07-2013 16:32:02

FILE NAME =	USER NAME = HECHTBR	DESIGNED -	REVISED -
FILEL		DRAWN - AMB	REVISED -
	PLOT SCALE = *SCALE*	CHECKED - BRH	REVISED -
	PLOT DATE = *DATE*	DATE - 11/01/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
 U.S. ROUTE 14

PROPOSED SIGN SCHEDULE - II			
SCALE: N.T.S.	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	27R-2	MCHENRY	673	391
CONTRACT NO. 62268			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

