

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | |
|---------------------|---|-----------------|----------------|------------------------------|--------------------------|
| | | | | 100% STATE | 100% STATE |
| | | | | ROADWAY 0005 IROQUOIS COUNTY | ROADWAY 0005 FORD COUNTY |
| 20200600 | EXCAVATING AND GRADING EXISTING SHOULDER | UNIT | 385 | 204 | 181 |
| 20400800 | FURNISHED EXCAVATION | CU YD | 34 | 12 | 22 |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 165 | 30 | 135 |
| 25200200 | SUPPLEMENTAL WATERING | UNIT | 4.4 | 0.8 | 3.6 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 25 | 11 | 14 |
| 40600527 | LEVELING BINDER (HAND METHOD), IL-9.5FG, N50 | TON | 42 | 19 | 23 |
| 40600627 | LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50 | TON | 3580 | 1616 | 1964 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 1 | 1 |
| 40600990 | TEMPORARY RAMP | SQ YD | 192 | 64 | 128 |
| 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 7159 | 3231 | 3928 |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 870 | 293 | 577 |
| 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SQ FT | 3568 | 1928 | 1640 |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 272 | 144 | 128 |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 82748 | 37349 | 45399 |

| | | | | | | | | | | | |
|---------------------|-------------------|------------|-----------|---|-----------------------|---------------------------|-------------------|------------|--------------|-----------|--|
| FILE NAME * | USER NAME * USER# | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | P.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| FILE# | | DRAWN - | REVISED - | | | 338 | 133RS-5 & 132RS-3 | IROO./FORD | 19 | 3 | |
| PLOT SCALE * SCALE# | | CHECKED - | REVISED - | | | CONTRACT NO. 66809 | | | | | |
| PLOT DATE * DATE# | | DATE - | REVISED - | | | ILLINOIS FED. AID PROJECT | | | | | |

Rev.