

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	100% STATE
				ROADWAY 0005 IROUOIS COUNTY	ROADWAY 0005 FORD COUNTY
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	180	63	117
44000600	SIDEWALK REMOVAL	SO FT	3268	1548	1720
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1253	609	644
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	6424	3400	3024
60255500	MANHOLES TO BE ADJUSTED	EACH	4	0	4
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	142	50	92
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	1	1
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5	0.5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	7696	3551	4145
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	320	0	320

FILE NAME * #FILE#	USER NAME * #USER#	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S. RFE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - _____	REVISED - _____					338	133RS-5 & 132RS-3	IROO./FORD	19	4
		CHECKED - _____	REVISED - _____		SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 66B09				
		DATE - _____	REVISED - _____					ILLINOIS FED. AID PROJECT				