

SIDEWALK SCHEDULE FOR NEW RAMP INSTALLATION									
LOCATION SIDE STREET QUAD	STANDARD NUMBER	PCC SIDEWALK 4"	DETECTABLE WARNINGS		CC&G TYPE B 6.24 FOOT	SIDEWALK REMOVAL SO FT	CC&G REMOV FOOT	SOD, SALT TOLERANT SO YD	SUPPLEMENTAL WATERING UNIT
			US 45 ACCESS SO FT	SIDE ROAD ACCESS SO FT					
IROUOIS COUNTY									
IST STREET		SO FT	SO FT	SO FT	FOOT	SO FT	FOOT	SO YD	UNIT
S.E.	424001-6 <5'	200.0	8.0	8.0	10.0	200.0	10.0	8.0	0.22
ALLEY									
E	424006	180.0		32.0		180.0			
ALLEY									
E	424006	288.0		32.0		288.0			
ADAMS ST.									
N.E.	424001-6 >5'	160.0		8.0	10.0	160.0	10.0	3.0	0.08
S.E.	424001-6 >5'	200.0		8.0		200.0	5.0		
WASHINGTON ST.									
N.W.	424001-6 >5'	50.0	8.0		10.0	50.0	10.0	8.0	0.22
N.E.	424001-6 <5'	550.0	8.0	8.0	20.0	220.0	20.0		
S.E.	424001-6 <5'	200.0	8.0	8.0		150.0	8.0	3.0	0.08
VIRGINIA ST.									
S.E.	424001-6 >5'	100.0	8.0			100.0		8.0	0.22
TOTAL(ALL IROUOIS)		1928.0	40.0	104.0	50.0	1548.0	63.0	30.0	0.8
FORD COUNTY									
PINE ST									
N.E.	424001-6 >5'	20.0		8.0	10.0	20.0	5.0	5.0	0.14
S.E.	424001-6 >5'	20.0		8.0	10.0	20.0	30.0	10.0	0.27
HOLMES ST.									
N.E.	424001-6 <5'	240.0	8.0	8.0		240.0	15.0	20.0	0.54
S.E.	424001-6 <5'	300.0	8.0	8.0		300.0			
STATE ST.									
N.E.	424001-6 >5'	150.0		8.0	30.0	150.0	25.0	15.0	0.41
S.E.	424001-6 >5'	150.0		8.0	20.0	150.0	20.0	3.0	0.08
PELLS ST.									
OMIT									
PATTON ST									
OMIT									
E FRANKLIN ST.									
N.E.	424001-6 >5'	40.0				40.0		8.0	0.22
S.E.	424001-6 <5'	25.0			12.0	75.0	12.0	8.0	0.22
E OTTAWA ST.									
N.E.	424001-6 >5'	60.0		8.0		90.0		8.0	0.22
S.E.	424001-6 >5'	260.0	8.0	8.0	10.0	260.0	10.0	8.0	0.22
E SUMMER ST.									
N.E.	424001-6 >5'	60.0		8.0		60.0		10.0	0.27
S.E.	424001-6 >5'	105.0		8.0		105.0		10.0	0.27
LANE DR.									
N.E.	424001-6 >5'	75.0		8.0		75.0		10.0	0.27
S.E.	424001-6 >5'	75.0		8.0		75.0		10.0	0.27
DAWN AVE.									
N.E.	424001-6 >5'	60.0		8.0		60.0		10.0	0.27
TOTAL(ALL FORD)		1640.0	24.0	104.0	92.0	1720.0	117.0	135.0	3.6
GRAND TOTAL		3568.0	64.0	208.0	142.0	3268.0	180.0	165.0	4.5

ADJUSTMENTS	
LOCATION STATION	MANHOLES TO BE ADJUSTED (EACH)
IL 45 (FORD COUNTY)	
HOLMES ST.	1.0
STATE ST.	1.0
JUST NORTH OF PELL'S ST. (1 IS AN INLET)	2.0
TOTALS	4

HMA SHOULDER				
LOCATION	LENGTH	AREA	HMA SHOULDER 6"	EXCAVATING & GRADING EXISTING SHLD
STATION (RT&LT))	FT	SO YD	SO YD	UNIT
IROUOIS COUNTY				
2341+44 TO 2443+45	10201	3400	3400	204
TOTAL IROUOIS COUNTY	10201	3400	3400	204
FORD COUNTY				
2443+45 TO 2527+39	8393	2798	2798	168
STA EO 2527+38BK=0+00AH				
0+00 TO 4+34	434	145	145	9
1070+13+15	245	82	82	5
TOTAL FORD COUNTY	9072	3024	3024	181
TOTALS	19273	6424	6424	385

FILE NAME -	USER NAME - #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -		SCALE: _____	SHEET _____	OF _____	SHEETS	STA. _____	TO STA. _____	IROO./FORD	19	13
		CHECKED -	REVISED -								CONTRACT NO. 66B09		
		DATE -	REVISED -								ILLINOIS FED. AID PROJECT		