

SIDE ROAD & ENTRANCES									
NAME	MATERIAL	STATION	TYPE	RT/LT**	HMA SURF REM VAR DEPTH	INCIDENTAL HMA SURF	BIT MATLS PR CT	TEMP. RAMP FOR SIDEROAD	FURN. EX*
					SO YD	TON	POUND	SO YD	CU YD
IROOOUIS COUNTY									
IST STREET	HMA	2325+08	SR	RT/LT	405	45.4	273.4	8.00	2.0
	HMA	2327+08	PE	LT	22.5	2.5	15.2		
ADAMS ST.	HMA	2327+82	SR	LT	257	28.8	173.5	8.00	2.0
	GRAVEL	2351+49	CE	RT		0.0	0.0		
	PCC	2329+32	CE	LT		0.0	0.0		
	GRAVEL	2329+42	CE	RT		0.0	0.0		
	PCC	2330+02	PE	LT		0.0	0.0		
WASHINGTON ST.	HMA	2334+58	SR	RT/LT	477	53.4	322.0	8.00	2.0
	PCC	2336+58	CE	LT		0.0	0.0		
JACKSON ST.	HMA	2339+28	SR	LT	376	42.1	253.8	8.00	2.0
	HMA	2340+92	PE	LT	20	2.2	13.5		
VIRGINIA ST.	HMA	2342+72	SR	LT	300	33.6	202.5	8.00	2.0
	GRAVEL	2362+04	PE	LT		0.0	0.0		
	HMA	2378+88	PE/MB	LT	25	2.8	16.9		
100 N	HMA	2388+44	SR	RT/LT	666	74.6	449.6	8.00	2.0
	HMA	2414+84	PE	LT	25	2.8	16.9		
	HMA	2417+24	PE/MB	RT	45	5.0	30.4		
IROOOUIS CO. TOTAL					2619	293	1767	48	12
FORD COUNTY									
000 N	HMA	2441+24	SR	RT/LT	847	94.9	571.7	8.00	2.0
	HMA	2446+52	PE	LT	25	2.8	16.9		
	HMA	2446+52	MB	RT	20	2.2	13.5		
500 N	HMA	2501+82	SR	RT/LT	693	77.6	467.8	8.00	2.0
	PCC	2504+82	PE	LT		0.0	0.0		
	PCC	2506+07	PE	LT		0.0	0.0		
	HMA	2515+66	CE	LT	195	21.8	131.6		
	HMA	2518+66	CE	LT	195	21.8	131.6		
CHESTNUT ST.	HMA	0+00	SR	LT	243	27.2	164.0	8.0	2.0
SPRUCE ST.	HMA	5+00	SR	LT	260	29.1	175.5	8.0	2.0
	HMA	5+28	CE	LT	48	5.4	32.4		
PINE ST.	HMA	5+88	SR	LT	248	27.8	167.4	8.0	2.0
	HMA	6+48	CE	LT	102	11.4	68.9		
HOLMES ST.	HMA	12+56	SR	LT	275	30.8	185.6	8.0	2.0
HOLMES ST.	PCC	12+56	SR	RT		0.0	0.0		
STATE ST.	HMA	16+84	SR	LT	343	38.4	231.5		
	PCC	17+44	CE	LT		0.0	0.0		
	PCC	18+04	CE	LT		0.0	0.0		
	PCC	18+24	CE	LT		0.0	0.0		
	PCC	20+74	CE	LT		0.0	0.0		
	PCC	35+09	CE	LT		0.0	0.0		
	PCC	36+34	CE	LT		0.0	0.0		
	PCC	37+34	CE	LT		0.0	0.0		
FRANKLIN ST.	HMA	39+10	SR	LT	300	33.6	202.5	8.0	2.0
	PCC	40+48	CE	LT		0.0	0.0		
	PCC	40+69	CE	LT		0.0	0.0		
	PCC	41+49	CE	LT		0.0	0.0		
	PCC	43+49	CE	LT		0.0	0.0		
OTTAWA RD.	HMA	44+55	SR	LT	364	40.8	245.7	8.0	2.0
	PCC	45+87	CE	LT		0.0	0.0		
	PCC	48+27	CE	LT		0.0	0.0		
	PCC	50+85	CE	LT		0.0	0.0		
	PCC	52+45	CE	LT		0.0	0.0		
SUMMER ST.	HMA	55+25	SR	LT	333	37.3	224.8	8.0	2.0
	PCC	55+53	CE	LT		0.0	0.0		
LANE DR.	HMA	56+51	SR	LT	315	35.3	212.6	8.0	2.0
	PCC	59+03	PE	LT		0.0	0.0		
	PCC	60+53	PE	LT		0.0	0.0		
	PCC	61+61	PE	LT		0.0	0.0		
	PCC	65+14	PE	LT		0.0	0.0		
DAWN AVE.	HMA	67+55	SR	LT	343	38.4	231.5	8.0	2.0
FORD CO. TOTAL					5149	577	3476	88	22
TOTALS					7768	870	5243	136	34

*PLACE FURNISHED EX AROUND SIDEROAD RADII. THIS AREA TO BE SEEDED, FERTILIZED AND MULCHED- NOT PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EX

**RT/LT, FACING EAST

ALL MAILBOX TURNOUTS TO BE MILLED AND PAVED. ONLY THOSE MBTO ON OPPOSITE SIDE OF ROADS ARE BROKEN OUT ABOVE

FILE NAME -	USER NAME - #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
#FILE#		DRAWN -	REVISED -		SCALE: _____	SHEET _____	OF _____	SHEETS	STA. _____	TO STA. _____	338	(331RS-5 & 1321RS-3)	IROO./FORD	19	14
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		CONTRACT NO. 66809										
	PLOT DATE = #DATE#	DATE -	REVISED -		ILLINOIS FED. AID PROJECT										