

MAINLINE SCHEDULE											
LOCATION		LENGTH FOOT	AGG SHLD TYPE B	BIT MATL (PR CT)	MIX CR, JTS, & FLGWY	LEV BIND (HM) N50	LEV BIND (MM) N50	HMA SURF CSE "D", N50	HMA SURFACE REMOVAL		TEMP RAMP
STA	TO STA		TON	POUND	TON	TON	TON	TON	1 1/2"	BUTT JT	SQ YD
988+91	TO 989+21	30	6	64	0.03	0.05	4	8	93		31
989+21	TO 1055+65	6644	1262	14152	6.20	10.34	881	1736	20670		
1055+65	TO 1055+95	30	6	64	0.03	0.05	4	8		93	31
TOTALS			1274	14280	6.3	10.4	889	1752	20763	93	62

SIDEROAD AND ENTRANCE SCHEDULE														
STATION	SIDE	TYPE	MATERIAL	WIDTH	LENGTH	AREA	INCID HMA SURF	BIT MATL (PR CT)	TEMP RAMP	FURN EXC	EROS CONT BLKT	AGG SURF CSE TY B	HMA SURF REM 1 1/2"	
				FOOT	FOOT	SQ FT								TON
996+05	LT	CE	HMA	26	10	700	9	35		3	15		78	
996+05	RT	CE	CONCRETE	35	NO WORK - MATCH PROP HMA SHLD RESURF TO CONCRETE ENTRANCE									
998+60	LT	FE	AGG	24	10	340				3	15	5		
1001+52	LT	PRITCHARD RD	HMA	24	43	1932	24	97	13	6	40		215	
1004+70	RT	FE	AGG	24	10	340				3	15	5		
1008+60	RT	MB/CE	HMA/CONC	38	26	1088	14	54					121	
1015+00	RT	CE	HMA	20	10	300	4	15		3	15		33	
1022+65	LT	FE	AGG	24	10	340				3	15	5		
1029+60	LT	FE	AGG	24	10	340				3	15	5		
1029+60	RT	FE	AGG	24	10	340				3	15	5		
1035+60	LT	FE	AGG	24	10	340				3	15	5		
1042+65	LT	PE	HMA	15	10	380	5	19		3	15		42	
1042+65	RT	MB	HMA	20	7	322	5	16		3	33		36	
1049+60	LT	FE	AGG	24	10	340				3	15	5		
TOTALS							61	236	13	39	223	35	525	

PAVEMENT MARKINGS											
LOCATION STATION TO STATION	POLYUREA TYPE 1 PAVEMENT MARKING			TEMPORARY PAVEMENT MARKINGS 2 APPLICATIONS			SHORT TERM PAVEMENT MARKING FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	RAISED REFL PAVT MARKERS 2-WAY AMBER EACH	RAISED REFL PAVT MARKER REMOVAL EACH	COMMENTS
	LINE - 4"		LINE - 6"	LINE - 4"		LINE - 6"					
	WHITE	YELLOW	YELLOW	WHITE	YELLOW	YELLOW					
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT					
988+91 TO 989+21	60	60		120	120		12	1	0	0	DOUBLE SOLID
989+21 TO 993+21	800	400	100	1600	800	200	160	13	5	5	NO PASS LT
993+21 TO 1055+95	12548		1570	25096		3140	2510	209	78	78	SKIP DASH
SUB-TOTALS	13408	460	1670	26816	920	3340	2682	223	83	83	
TOTALS	13868		1670	27736		3340	2682	223	83	83	

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pwork\pwork\duncanbd\0253031\0366818-sht-cover.dgn	DRAWN -	REVISED -	573						(117)RS-6	DEKALB	11	6	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 66B18						
PLOT DATE = 6/6/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT										