

CONSTRUCTION CODE
 CONTRACT MAINTENACE
 100% STATE
 BRIDGE
 0014
 RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SN: 038-0153 (SB)	SN: 038-0155 (SB)
				SN: 038-0154 (NB)	SN: 038-0156 (NB)
50102400	CONCRETE REMOVAL	CU YD	340.6	161.4	179.2
50300100	FLOOR DRAINS	EACH	30	16	14
50300255	CONCRETE SUPERSTRUCTURE	CU YD	381.8	184.8	197
50300300	PROTECTIVE COAT	SQ YD	877	377	500
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2428	1214	1214
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	101500	40560	60940
50800515	BAR SPLICERS	EACH	144	72	72
50800530	MECHANICAL SPLICERS	EACH	2148	732	1416
52000110	PREFORMED JOINT STRIP SEAL	FOOT	354	178	176
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1490	700	790
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1490	700	790
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	5136	2922	2214
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	2204	1054	1150
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2646	1340	1306
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2	1	1
X7010410	SPEED DISPLAY TRAILER	CAL MO	7	3.5	3.5
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	42	21	21

20 * SPECIALITY ITEMS