

SUMMARY OF QUANTITIES

LOCATION:

FUNDING BREAKOUT

CONSTRUCTION CODE:

FAP 1513 (IL 10)
STATION 299+59 TO
STATION 312+64.60
URBAN TWO-LANE
CHAMPAIGN
COUNTY

FAP 1513 (IL 10)
STATION 312+64.60
STATION 564+40.45
RURAL TWO-LANE
CHAMPAIGN
COUNTY

FAP 1513 (IL 10)
STATION 564+40.45 TO
STATION 637+60
RURAL TWO-LANE
PIATT
COUNTY

100% STATE

100% STATE

100% STATE

0005
07A0M

0005
07A0B

0005
07A0B

PAY ITEM CODE	PAY ITEM	UNIT	TOTAL	QTY	QTY	QTY
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FC, N50	TON	3,904.0	146.0	2,889.0	869.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	594.0	80.0	134.0	380.0
40600990	TEMPORARY RAMP	SQ YD	436.0	27.0	347.0	62.0
40603310	HOT MIX ASPHALT, SURFACE COURSE, MIX "C" N50	TON	7,543.0	293.0	5,512.0	1,738.0
40800050	INCIDENTAL HOT MIX ASPHALT SURFACING	TON	520.0	11.0	438.0	71.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	69,473.0	0.0	48,784.0	20,689.0
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	22.0	0.0	0.0	22.0
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	2,292.0	136	1,759.00	397
48203100	HOT-MIX ASPHALT SHOULDERS	TON	288.0	0	171.00	117
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3.0	1.0	1.0	1.0
67100100	MOBILIZATION	L SUM	1.0	0.0	0.7	0.3
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.0	0.7	0.3
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.0	0.7	0.3
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9,588.0	404.0	6,976.0	2,208.0

* SPECIALTY ITEMS

* D5 PATCH & RES 2014-7

FILE NAME =	USER NAME = ceerlockjd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\p\work\p\idot\ceerlockjd\20250170\0570841-ht-qa.dgn	DRAWN -	REVISED -	1513					*	CHAMP/PIATT	40	4	
PLOT SCALE = 48,0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 70841									
PLOT DATE = 5/15/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.