

SURFACE COURSE AND PRIME COAT SCHEDULE

STATION	TO	STATION	LENGTH	WIDTH		SQ YD	BITUMINOUS	HMA SURFACE
							PRIME COAT **	COURSE, MIX "C"
							X4060110	40603310
							POUND	TONS
URBAN								
299+59.00		312+64.6	1305.60	24.00	=	3,481.60	2,350.1	292.5
RURAL								
312+64.60		381+81.0	6916.40	24.00	=	18,443.73	12,449.5	1,549.3
END OVERLAY/BEGIN INLAY								
381+81.00		385+93.0	412.00	35	*	=	1,602.22	1,081.5
385+93.00		398+04.0	1211.00	35	*	=	4,709.44	3,178.9
398+04.00		401+99.0	395.00	35	*	=	1,536.11	1,036.9
401+99.00		484+71.7	8272.78	24	=	22,060.75	14,891.0	1,853.1
OMISSION FOR STRUCTURE								
486+65.22		487+68.51	103.29	24	=	275.44	185.9	23.1
EQ. STA.								
500+69.80		564+40.4	6370.65	24	=	16,988.40	11,467.2	1,427.0
CHAMPAIGN TOTAL								
							2,350.1	292.5
URBAN							2,350.0	293.0
USE							44,290.9	5,511.8
RURAL							44,291.0	5,512.0
USE								
PIATT COUNTY								
564+40.45		624+44.0	6003.55	24	=	16,009.47	10,806.4	1,344.8
624+44.00		637+60.0	1316.00	32	=	4,679.11	3,158.4	393.0
PIATT TOTAL								
TOTAL							13,964.8	1,737.8
USE							13,965.0	1,738.0
TOTAL							60,606.0	7,543.0

* Converted from METRIC Plans

** TO BE APPLIED AT A RATE OF 0.05 LB/SQ FT ON MILLED SURFACES AND 0.025 LB/SQ FT AS FOG COAT
INCIDENTAL PRIME COAT WILL ALSO BE PAID AS X4060110

LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50

(40600627)

STATION	TO	STATION	LENGTH	WIDTH	SQ YD	TONS
URBAN						
299+59.0	TO	312+64.60	1,305.6	24	3,481.6	146.2
RURAL						
312+64.60		381+81.0	6,916.4	24	18,443.7	774.6
END OVERLAY/BEGIN INLAY						
381+81.0	TO	385+93.00	412.0	35	1,602.2	67.3
385+93.0	TO	390+53.00	460.0	35	1,788.9	75.1
OMISSION FOR CURB AND GUTTER						
URBAN						
393+50.00		398+04.0	454.0	35	1,765.6	74.2
398+04.00		401+99.0	395.0	35	1,536.1	64.5
401+99.00		445+65.0	4,366.0	35	16,978.9	713.1
omission for curb and gutter						
449+45.00		484+71.7	3,526.8	24	9,404.7	395.0
OMISSION FOR STRUCTURE						
486+65.22		487+69.51	104.3	24	278.1	11.7
EQ. STA.						
500+69.80		564+40.4	6,370.6	24	16,988.4	713.5
CHAMPAIGN TOTAL						
						146.2
URBAN						146
USE						2,889.0
RURAL						2889
USE						
PIATT COUNTY						
564+40.45		624+44.0	6,003.6	24	16,009.5	672.4
624+44.00		637+60.0	1,316.0	32	4,679.1	196.5
PIATT TOTAL						
TOTAL						868.9
USE						869.0
TOTAL						3,904.0

• D5 PATCH & RES 2014-7

FILE NAME =	USER NAME = ceorlockjd	DESIGNED -	REVISED -	STATE OF ILLINOIS	SCHEDULE OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ce:\pw\work\p\dot\ceorlockjd\0285170\0570841-sht-schedules.dgn		DRAWN -	REVISED -	DEPARTMENT OF TRANSPORTATION		1513	*	CHAMP/PIATT	40	14
	PLOT SCALE = 48.0000' / in.	CHECKED -	REVISED -							
	PLOT DATE = 5/15/2014	DATE -	REVISED -		SCALE: _____	SHEET 1	OF 6	SHEETS	STA. _____	TO STA. _____
										ILLINOIS FED. AID PROJECT
										CONTRACT NO. 70841