

HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"
(44000155)

STA.	LENGTH	WIDTH	SQ FT	SQ YD
300+19.00				
(MICROSURFACING OVERLAY, NO MILLING THIS SECTION)				0.00
381+81.00	412.00	41.00	16,892.00	1,876.89
385+93.00	1,211.00	41.00	49,651.00	5,516.78
398+04.00	395.00	41.00	16,195.00	2,062.78
401+99.00	8,272.78	24.00	198,546.72	22,060.75
484+71.78				
OMISSION FOR STRUCTURE				
486+65.22	104.29	24.00	2,502.96	278.11
487+69.51				
EQ.STA.				
500+69.80				
PIATT COUNTY	6,370.65	24.00	152,895.60	16,988.40
564+40.45	6,003.55	24.00	144,085.20	16,009.47
624+44.00	1,316.00	32.00	42,112.00	4,679.11
637+60.00				
CHAMPAIGN				
URBAN				0.00
USE				0.00
RURAL				48783.70
USE				48784.00
PIATT				20688.58
USE				20689.00
TOTAL				69473.00

AGGREGATE SHOULDER WEDGE, TYPE B
(48102100)

STATION	LENGTH	SQ YD	AVERAGE THICKNESS (INCH)*	TONS
STA. 299+59.00				
	1,305.60	435.20	3.125	136.00
STA. 312+64.60				
	6,916.40	2,740.67	3.125	856.46
STA. 381+81.00				
	412.00	137.33	1.625	22.32
STA. 385+93.00				
	1,211.00	403.67	1.625	65.60
STA. 398+04.00				
	395.00	131.67	1.625	21.40
STA. 401+99.00				
	8,272.78	2,757.59	1.625	448.11
STA. 484+71.78				
EQ. STA.				
STA. 500+69.80				
	6,370.65	2,123.55	1.625	345.08
STA. 564+40.45				
	7,319.55	2,439.85	1.625	396.48
STA. 637+60.00				
TOTALS	32,202.9	11,169.53		2,291.43
CHAMPAIGN				
URBAN 136.00 TONS				
USE 136 TONS				
RURAL 1,758.95 TONS				
USE 1,759.00 TONS				
PIATT 396.48 TONS				
USE 397 TONS				
TOTAL 2,292.00 TONS				

* Shoulders were approximately 1 1/2 inch low throughout, actual shoulders at time of resurfacing may vary.