

## PAINT PAVEMENT MARKINGS, AND RAISED REFLECTIVE MARKERS(CONT)

STA	LENGTH	PAINT PAVEMENT MARKING LINE, 4" (78001110)			RAISED REFLECTIVE PAVEMENT MARKERS (78100100)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (78300200)
		SKIP DASH 4" YELLOW FOOT	4" WHITE FOOT	NO PASSING 4" YELLOW FOOT	RRPM AMBER EACH	RRPM WHITE EACH	
418+78.00	2,739.00	684.75	5,478.0		35		35
446+17.00							
SEYMORE RD	178.00	44.50					
447+95.00	3,974.51	993.63	7,949.0		51		51
487+69.51							
EQ STA							
500+69.80	2,030.20	507.55	4,060.4		26		26
521+00.00	1,150.00	287.50	2,300.0	1,150.00	15		15
532+50.00	650.00		1,300.0	1300	9		9
539+00.00	1,300.00	325.00	2,600.0	1,300.00	17		17
552+00.00	1,240.45	310.11	2,480.9		16		16
564+40.45							
<b>SUBTOTAL</b>	<b>25,388.9</b>	<b>5,754.3</b>	<b>46,422.3</b>	<b>3,750.0</b>	<b>388.68</b>	<b>8.00</b>	
			<b>55,927.0</b>				
<b>URBAN USE</b>		<b>2948</b>	<b>2,947.6</b>		<b>17.32</b>		<b>17.32</b>
<b>RURAL USE</b>			<b>52,979.0</b>		<b>396.68</b>		<b>396.68</b>
		<b>52,979.0</b>			<b>397.00</b>		<b>397</b>
<b>PIATT COUNTY</b>							
564+40.45	2,259.55	564.89	4,519.1		30		30
587+00.00	1,050.00	262.50	2,100.0	1,050.00	14		14
597+50.00	500.00		1,000.0	1000	7		7
602+50.00	1,350.00	337.50	2,700.0	1,350.00	17		17
616+00.00	844.00	211.00	1,688.0				
624+44.00	1,316.00		2,632.0	2632	17		17
637+60.00							
RAMP C	108.00		108.00	108.00			
RAMP D	179.31		179.31	179.31			

## PAINT PAVEMENT MARKINGS, AND RAISED REFLECTIVE MARKERS (CONT)

STA	LENGTH	PAINT PAVEMENT MARKING LINE, 4" (78001110)			RAISED REFLECTIVE PAVEMENT MARKERS (78100100)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (78300200)
		SKIP DASH 4" YELLOW FOOT	4" WHITE FOOT	NO PASSING 4" YELLOW FOOT	RRPM AMBER EACH	RRPM WHITE EACH	
<b>SUBTOTAL</b>	<b>7,606.86</b>	<b>1,375.89</b>	<b>14,926.41</b>	<b>6,319.31</b>	<b>85.00</b>	<b>0.00</b>	<b>85</b>
		<b>22,622.00</b>					
<b>TOTAL</b>	<b>32,995.75</b>	<b>7,130.18</b>	<b>61,348.73</b>	<b>10,069.31</b>	<b>491.68</b>	<b>8.00</b>	<b>500</b>
			<b>78,549.00</b>		<b>500.00</b>		

## PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS (78003100)

CHAMPAIGN COUNTY		
TURN ARROWS		SQ FT
388+68.00	*	15.6
389+39.00	*	15.6
390+01.49	*	15.6
390+70.00	*	15.6
391+35.00	*	15.6
392+63.00	*	15.6
393+24.00	*	15.6
393+98.48	*	15.6
394+59.00	*	15.6
395+28.00	*	15.6
<b>TOTAL</b>		<b>156.0</b>

\*Stations converted from metric Plans

\* D5 PATCH & RES 2014-7