

CONSTR. CODE  
 URBAN  
 80% FEDERAL  
 20% STATE  
 BRIDGE  
 0014  
 001-0068

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
50102400	CONCRETE REMOVAL	CU YD	67.8	67.8
50157300	PROTECTIVE SHIELD	SQ YD	87	87
50300255	CONCRETE SUPERSTRUCTURE	CU YD	64.6	64.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	13770	13770
50800515	BAR SPLICERS	EACH	156	156
50800530	MECHANICAL SPLICERS	EACH	672	672
52100540	ANCHOR BOLTS, 1 1/2"	EACH	25	25
59000200	EPOXY CRACK INJECTION	FOOT	120	120
67100100	MOBILIZATION	L SUM	1	1
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1150	1150

FILE NAME :	USER NAME : eparkegn	DESIGNED -	REVISED -
c:\p\work\p\d\at\eparkgn\d0381163\0672080-sh1-300.dgn		DRAWN -	REVISED -
	PLOT SCALE * 100.0000 * / IN	CHECKED -	REVISED -
Default	PLOT DATE * May-12-2014 08:56:33AM	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET 1	OF 2 SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
63	(12-B)BJR.1-7	ADAMS	31	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72680	