

AGGREGATE SHOULDERS TYPE B			
LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	(TONS)
FAS 1741 (FR I-55 WEST)			
LEFT			
STA. 1405+50.00 TO STA. 1499+80.00	9,430.00	6	1381.5
RIGHT			
STA. 1405+50.00 TO STA. 1499+80.00	9,430.00	6	1381.5
TOTAL			2,763.0

PAVEMENT MARKING							
LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	LINE-5"		YELLOW (FT)	WHITE (FT)
FAS 1741 (FR I-55 WEST)							
STA. 1405+50.00 TO STA. 1499+80.00	SKIP-DASH (CENTER)	9430.00	10' @ 40'			2,358.00	-
STA. 1405+50.00 TO STA. 1499+80.00	SOLID (EDGE LINE RT)	9430.00	-			-	9,430.00
STA. 1405+50.00 TO STA. 1499+80.00	SOLID (EDGE LINE LT)	9430.00	-			-	9,430.00
TOTAL						2,358.00	18,860.00

PAVEMENT SCHEDULE								
LOCATION STATION TO STATION	LENGTH	WIDTH	PCC SURF. REM. BUTT-JOINT (SQ YD)	HMA SURF. REM. BUTT-JOINT (SQ YD)	HMA BINDER COURSE IL-19.0 N50 (2 1/4") (TON)	HMA SURF. COURSE MIX "C" N50 (1 1/2") (TON)	BIT. MAT. PRIME CT. (TON)	
FAS 1741 (FR I-55 WEST)								
STA. 1405+50.00 TO STA. 1406+25.00	75.00	24	200.00	-	25.20	16.80	0.15	
STA. 1406+25.00 TO STA. 1499+05.00	9280.00	24	-	-	3118.10	2078.70	9.35	
STA. 1499+05.00 TO STA. 1499+80.00	75.00	24	-	200.00	25.20	16.80	0.15	
TOTAL			200.00	200.00	3244.00***	2112.30	9.65	

***75 TONS OF HMA BINDER COURSE, IL-19.0, N50 ADDED TO QUANTITY FOR SUPER ELEVATION ADJUSTMENT

SIDEROAD AND ENTRANCE SCHEDULE									
LOCATION FAS 1741 (FR I-55 WEST)	WIDTH ACROSS FRONT (FT)	WIDTH ACROSS BACK (FT)	LENGTH OF IMPROVEMENT FROM EOP (FT)	EXIST. SURF. TYPE	PREPARATION OF BASE (SQ YD)	PCC SURF. REM. BUTT-JOINT (SQ YD)	HMA SURF. REM. BUTT-JOINT (SQ YD)	INCIDENTAL HOT-MIX ASPH. SURF. (TON)	BIT. MAT. PRIME COAT (TON)
P.E. W/M.B.T. RT. STA. 1428+56	62	14	8	AGG	33.81	-	-	6.62	0.05
GOBY AVE. RT. STA. 1441+78	44	24	10	HMA	-	-	38.00	16.95	0.05
M.B.T. RT. STA. 1442+24	64	10	8	AGG	32.92	-	-	6.45	0.05
C.E. RT. STA. 1444+83	44	24	10	CONC	-	37.78	-	16.91	0.05
P.E. W/M.B.T. RT. STA. 1456+05	62	15	8	AGG	34.27	-	-	6.71	0.05
P.E. RT. STA. 1497+53	24	12	8	CONC	-	16.11	-	3.18	0.05
P.E. RT. STA. 1498+57	24	12	8	CONC	-	16.11	-	3.18	0.05
TOTAL					101.00	70.00	38.00	60.00	0.35

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\idot\sparksgw\10397716\0672\h06-sht-schedule.dgn	DRAWN -	REVISED -	REVISED -						1741	***	MONTGOMERY	14	5
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 72H06	
	PLOT DATE = May-20-2014 11:31:19AM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								