

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING - 4"		THERMOPLASTIC PAVEMENT MARKING - 6"		THERMOPLASTIC PAVEMENT MARKING - 8"		THERMOPLASTIC PAVEMENT MARKING - 12"		THERMOPLASTIC PAVEMENT MARKING - LINE 24"		SHORT TERM PAVEMENT MARKING		WORK ZONE PAVEMENT MARKING REMOVAL	DESCRIPTION	
	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW	SO FT				
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT			
US 36 WESTBOUND	617+00.00	628+18.50			1119					12	224	89	39	PASSING LANE	
	628+55.00	639+50.00			1095						219	88	39	PASSING LANE	
	617+00.00	627+09.00	1009.00						12	80			10	DRIVING LANE	
	629+09.00	639+50.00	1041.00							83			10	DRIVING LANE	
	617+00.00	639+50.00			563					450			56	CENTERLINE	
	628+84.00	633+15.00			431			12	86				11	TURNLANE	
	SUB TOTAL		2050	2214	994			36	1142	177	165				
	US 36 EASTBOUND	617+00.00	628+18.50			1119						90	11	11	PASSING LANE
628+55.00		639+50.00			1095				12		88	11	11	PASSING LANE	
617+00.00		639+50.00	2250.00							180			23	DRIVING LANE	
617+00.00		639+50.00			562			12	450				56	CENTERLINE	
624+90.00		627+81.00			291			12	58				7	TURNLANE	
SUB TOTAL		2250	2214	853			36	688	178	108					
HARRISTOWN BLVD		216+34.00	217+18.25	197	0	20	173	155	352	68	24	20	11	4	
	SUB TOTAL		197	0	20	173	155	352	68	24	20	11	4		
GRAND TOTAL		4497	4427	1867	173	155	352	68	96	1850	366	277			

PAVING SCHEDULE

LOCATION	STATION TO STATION	LENGTH (FOOT)	LEVELING BINDER (MACHINE METHOD), N90	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SHOULDERS	BITUMINOUS MATERIALS (PRIME COAT)	
			QUANTITY (TON)	QUANTITY (SQ YD)	QUANTITY (SQ YD)	QUANTITY (TON)	QUANTITY (TON)	QUANTITY (TON)	QUANTITY (POUND)	
US 36 WESTBOUND	617+00.00	626+92.00	992.00	148.14	133.335	37.33	222.21	11.57	246.90	2380.8
	626+92.00	627+55.00	63.00	13.72			20.58	0.74	15.68	220.5
	627+55.00	628+16.00	61.00	17.46			26.19	0.36	5.69	280.6
	628+16.00	628+57.00	41.00	11.74			17.60	0.00	0.00	188.6
	628+57.00	628+86.00	29.00	8.30			12.45	0.17	2.71	133.4
	628+86.00	629+28.00	42.00	10.71			16.07	0.49	10.45	172.2
	629+28.00	633+25.00	397.00	88.93			133.39	4.63	98.81	1429.2
	633+25.00	635+16.50	191.50	35.75			53.62	2.23	47.66	574.5
	635+16.50	638+50.00	333.50	49.80			74.70	3.89	83.00	800.4
	638+50.00	639+50.00	100.00	14.93			22.40	1.00	19.91	240
US 36 EASTBOUND	617+00.00	621+53.04	453.04	67.65	133.335	37.33	101.48	5.285466667	112.76	1087.30
	621+53.04	624+80.00	326.96	61.03			91.55	3.814533333	81.38	980.88
	624+80.00	627+92.00	312.00	69.89			104.83	3.64	77.65	1123.20
	627+92.00	628+80.00	88.00	35.04			52.57	1.026666667	13.69	563.20
	628+80.00	631+47.00	267.00	56.49			84.73	3.115	66.45	907.80
	631+47.00	638+50.00	703.00	104.98			157.47	8.201666667	174.97	1687.20
	638+50.00	639+50.00	100.00	14.93			22.40	1	19.91	240.00
HARRISTOWN BLVD	216+64.00	216+73.00	20.00	12.04	401.11	38.89	33.69	0.58	21.00	361.00
TOTAL			822	668	114	1248	52	1099	13371	