

ALTERNATE BID SUMMARY OF QUANTITIES

M001L,01,0003,A		M001C,01,0003,A		M001L,01,0003,B		M001C,01,0003,B	
CONSTRUCTION CODE							
SALINE 80% FED. 20% STATE ROADWAY 0003		SALINE 80% FED. 20% STATE ROADWAY 0003		SALINE 80% FED. 20% STATE ROADWAY 0003		SALINE 80% FED. 20% STATE ROADWAY 0003	
ALTERNATE A URBAN		ALTERNATE A RURAL		ALTERNATE B URBAN		ALTERNATE B RURAL	

CODE NO.	ITEM	UNIT	ALTA TOTAL QUANTITY	ALTERNATE A URBAN	ALTERNATE A RURAL	ALTB TOTAL QUANTITY	ALTERNATE B URBAN	ALTERNATE B RURAL
20400100	BORROW EXCAVATION	CU YD	83,430	3,410	80,020	118,635	3,410	115,225
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	18,996	687	18,309	785	687	98
<del>40300100</del>	<del>BITUMINOUS MATERIALS (PRIME COAT)</del>	<del>GALLON</del>	<del>82,728</del>	<del>9,557</del>	<del>73,171</del>	<del>13,407</del>	<del>9,557</del>	<del>3,850</del>
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2,635	2,487	148	2,487	2,487	
40701906	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/4"	SQ YD	166,480	19,491	146,989	19,491	19,491	
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	0			150,098		150,098
42101300	PROTECTIVE COAT	SQ YD	0			225,398		225,398
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	83,840	3,425	80,415	4,625	3,425	1,200
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	0			78,225		78,225
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	486,939	41,495	445,444	97,200	41,495	55,705
* X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	0			728		728
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	0			116,258		116,258
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	0			348		348
Z0034105	MATERIAL TRANSFER DEVICE	TON	51,580	8,217	43,363	8,217	8,217	

\* SPECIALTY ITEM

FILE NAME: P:\Projects\2011 Projects\11297 - I001 US 5 Ph2\CV\CADD Sheets\0978077-ht-500.dgn	USER NAME: bemory	DESIGNED: -	REVISIONS: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES ALTERNATE BID			F.A.P. RTE. 332	SECTION (29,301R-1)	COUNTY SALINE	TOTAL SHEETS 745	SHEET NO. 23
PLOT SCALE: 1/8" = 1' / m.	CHECKED: -	REVISIONS: -	SCALE: N.T.S.		SHEET NO. 18 OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 78077					
PLOT DATE: 1/28/2014	DATE: -	REVISIONS: -										