

R.O.W. & SURVEY MARKERS

LOCATION STATION TO STATION	SIDE	WOVEN WIRE FENCE	WOVEN WIRE GATES	FURNISHING AND ERECTING R.O.W. MARKERS EACH
STAGE 3				
U.S. 45				
447+00.00 TO 482+50.00	LT	3,681		18
460+01.07	LT		1	
447+00.00 TO 482+50.00	RT	3,480		12
459+94.52	RT		1	
482+50.00 TO 518+32.21	LT	3,235		4
482+50.00 TO 518+32.21	RT	3,271		17
492+76.36	RT		1	
507+17.28	RT		1	
512+17.03	RT		1	
516+32.21 TO 577+01.53	LT	6,013		12
540+32.29	RT		1	
516+32.21 TO 577+01.53	RT	5,764		4
523+87.76	RT		1	
529+58.65	RT		1	
541+84.12	RT		1	
563+04.93	RT		1	
577+01.53 TO 606+40.43	LT	2,830		4
577+01.53 TO 606+40.43	RT	2,825		4
597+73.02			1	
606+40.43 TO 649+37.28	LT	4,274		10
606+40.43 TO 694+67.60	RT	8,605		5
623+78.97	RT		1	
666+32.81	RT		1	
649+37.28 TO 694+67.60	LT	4,203		3
694+67.60 TO 710+94.32	LT	1,642		2
699+44.95	LT		1	
694+67.60 TO 711+86.46	RT	1,716		6
ALEXANDER RD.				
6+38.79 TO 10+00.00	RT	182		6
7+75.22	RT		1	
6+38.79 TO 10+00.00	LT	222		11
S. COOK RD.				
10+00.00 TO 13+80.34	RT	258		13
10+00.00 TO 13+80.34	LT	180		16
GANDERTOWN RD.				
20+15.00 TO 25+80.00	RT			11
20+42.47 TO 25+80.00	LT			5
BOURLAND				
6+96.12 TO 10+00.00	RT	154		6
6+96.12 TO 10+00.00	LT	124		7
COOK RD. N.				
10+00.00 TO 13+55.96	RT	235		1
10+00.00 TO 13+55.96	LT	196		2
11+74.97	LT		1	
SHILOH RD.				
10+00.00 TO 15+35.29				11
10+00.00 TO 14+97.79				9
CARTER FARM RD.				
6+39.48 TO 10+00.00	RT	254		5
7+17.54 TO 10+00.00	LT	118		6
8+04.08	LT		1	
VANGAMPLER RD.				
10+00.00 TO 13+65.56	RT	262		10
10+00.00 TO 13+65.56	LT	191		7
ABELL RD.				
10+00.00 TO 15+63.81	RT			10
10+00.00 TO 15+68.81	LT			8
UNTHANK RD.				
6+40.56 TO 10+00.00	RT	248		4
6+40.56 TO 10+00.00	LT	269		7
FLANDERS RD.				
10+00.00 TO 13+72.47	RT	273		9
10+00.00 TO 13+72.47	LT	214		8
GARNER RD.				
6+44.44 TO 10+00.00	RT	216		4
6+44.44 TO 10+00.00	LT	236		2
TEXAS CITY RD.				
6+51.13 TO 10+00.00	RT	87		3
6+51.13 TO 10+00.00	LT	184		2
COTTONWOOD RD.				
10+00.00 TO 13+70.23	RT	271		9
10+00.00 TO 13+70.23	LT	208		11
PROJECT TOTALS		56,120	17	304

SIGNS

LOCATION	NAME	SIGN PANEL TYPE 1		TELESCOPING STEEL SIGN SUPPORT FOOT	
		NO.	SQ. FT.		
STAGE 1A					
BIKE PATH					
403+48	LT	MILE 182	D10-3	2.50	13.00
403+48	LT	MILE 182	D10-3	2.50	-
423+10	LT	NO MOTOR VEHICLES	R5-3	4.00	12.00
423+20	RT	STOP SIGN	R1-1	2.25	11.50
ALEXANDER RD.					
8+60	RT	BIKE ROUTE	D11-1	3.00	14.25
8+60	RT	BIKE ROUTE ARROW	M6-1	0.75	-
9+10	LT	BIKE ROUTE	D11-1	3.00	14.25
9+10	LT	BIKE ROUTE ARROW	M6-1	0.75	-
U.S. 45					
406+65	45' LT	STOP SIGN	R1-1	2.25	-
406+65	45' LT	NO MOTOR VEHICLES	R5-3	4.00	12.00
STAGE 1B					
U.S. 45					
406+80	40' RT	STOP SIGN	R1-1	2.25	-
406+80	40' RT	NO MOTOR VEHICLES	R5-3	4.00	12.00
PROJECT TOTAL				31.25	89.00

ROADWAY BARRIERS

LOCATION STATION TO STATION	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 5A
	FOOT	FACH	FACH
STAGE 1A			
U.S. 45			
403+81.52 TO 404+31.52	LT	1	
404+31.52 TO 404+94.02	LT		
404+94.02 TO 405+23.76	LT		1
405+66.96 TO 405+69.75	LT		1
405+69.75 TO 405+76.36	LT		
FOURTH ST. NORTH			
7+87.54 TO 8+37.54	LT	1	
8+37.54 TO 8+81.31	LT		1
7+91.33 TO 8+41.33	RT	1	
8+41.33 TO 8+85.10	RT		1
PROJECT TOTAL		75.0	4

FILE NAME =	USER NAME = bemory	DESIGNED -	REVISED -
P:\Projects\2011 Projects\11297 - IDOT US 45 Ph2\CV\CADD Sheets\0978077-sht-schedule.dwg		DRAWN -	REVISED -
	PLOT SCALE = 100.00' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/30/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: N.T.S.	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(29,30)R-1	SALINE	745	62
CONTRACT NO. 78077				
ILLINOIS FED. AID PROJECT				