



TEMPORARY AGGREGATE SURFACE COURSE, TYPE B, 6" (34 TONS PER SIDE) FOR INFORMATION ONLY (SEE NOTE 1)

GENERAL NOTES

1. THE COST OF FURNISHING AND PLACING THE TEMPORARY AGGREGATE SURFACE COURSE, TYPE B, 6" IS INCLUDED IN THE COST OF THE PROPOSED PIPE CULVERT. THIS WORK SHALL BE PLACED AND COMPACTED TO THE SATISFACTION OF THE ENGINEER.
2. REMOVAL OF TEMPORARY AGGREGATE SURFACE IS INCLUDED IN THE COST OF EARTH EXCAVATION.
3. BACKFILL QUANTITY IS BASED ON THE USE OF SHORING. IF SHORING IS NOT USED THE ADDITIONAL BACKFILL WILL BE AT THE EXPENSE OF THE CONTRACTOR.
4. IF A TEMPORARY PATCH IS USED, THEN THE COST OF THE PATCH IS INCLUDED IN THE COST OF THE PROPOSED PIPE CULVERT. THE TEMPORARY PATCH SHALL HAVE A MINIMUM THICKNESS OF 2" BITUMINOUS MIXTURE MEETING THE ENGINEER'S APPROVAL.
5. THIS WORK WILL BE PERFORMED UNDER TRAFFIC CONTROL 701201 & 701336. NO OVER NIGHT LANE CLOSURES WILL BE PERMITTED.
6. PERMANENT PATCH SHALL BE PLACED WITHIN 5 DAYS OF PLACEMENT OF PROPOSED CULVERT. PERMANENT PATCH IS NOT INCLUDED IN THE COST OF THE PROPOSED CULVERT.
7. CONTRACTOR TO VERIFY GOOD WEATHER FORECAST PRIOR TO STARTING CONSTRUCTION.

CONSTRUCTING CULVERT UNDER TRAFFIC DETAIL

TO BE USED: STA 425+60 (5'x3' RCBC)
 STA 680+54 (24" RCP)
 STA 691+50 (30" EQUIV. ROUND SIZE RCP)

FILE NAME =	USER NAME = bemory	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DETAILS CONSTRUCTING CULVERT UNDER TRAFFIC	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
P:\Projects\2011 Projects\11297 - IDOT US 5 Ph2\CV\CADD Sheets\0978077-sht-details-p	DRAWN -	CHECKED -	REVISED -			332	(29,30)R-1	SALINE	745	484	
PLOT SCALE = 100.000' / in.	DATE -	REVISI	SCALE:			SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			
PLOT DATE = 4/30/2014	DATE -	REVISI	CONTRACT NO. 78077								