

RESURFACING SCHEDULE

LOCATION STATION TO STATION				LENGTH	ROADWAY WIDTH	ROADWAY AREA	HOT-MIX ASP. SURF. REMOV. 1 1/2"	TEMP RAMP	HOT-MIX ASP. SUR. CSE., MIX C, N 90 (1 1/2")	BIT. MAT. (PRIME COAT)	AGGREGATE WEDGE SHLDRS., TY. B	
				FOR INFORMATIONAL PURPOSE ONLY								
				(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(LBS)	(TON)	
FAP 780 (IL 34) Sta. 0+00 to Sta. 112+28.39												
MAINLINE	0+00	TO	1+19	119.0	26' & VAR.	809	809	132	68	364		
MAINLINE	1+19	TO	96+75	9556.0	24.0	25483	25483		2141	11467		
MAINLINE	96+75	TO	112+28	1553.0	24.0	4141	4142	23	348	1864		
PARK. LN. LT. & RT.	96+75	TO	112+28	1553.0	18.0	3106	3106		261	1398		
LEFT	1+19	TO	93+00	9181.0	2.0	2040					175.0	
RIGHT	0+80	TO	95+09	9429.0	2.0	2095					179.0	
PROJECT TOTALS							33,540	155	2818	15093	354.0	