



# Illinois Department of Transportation

Division of Aeronautics

1 Langhorne Bond Drive / Capital Airport / Springfield, Illinois / 62707-8415

July 25, 2014

SUBJECT: University of Illinois – Willard Airport  
Savoy, Illinois  
Champaign County  
Illinois Project Number: CMI-4347  
Contract No. UN053  
Item No. 11A, August 1, 2014  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 65 of the Special Provisions
2. Revised sheets 34, 35, 36, 64, 67, 80, 81 & 82 of the Plans.

### To All Plan Holders:

Replace page 65 of Special Provisions with Revised page 65

Replace Plan Sheet 34 with Revised Plan Sheet 34A

- Revise note to indicate location of EIN-3
- Revise note to indicate IN-3 as an Inlet Special

Replace Plan Sheet 35 with Revised Plan Sheet 35A

- Revise note to indicate that structure CS-5 is now called out as DC-3

Replace Plan Sheet 36 with Revised Plan Sheet 36A

- Revise all offsets to read with LT/RT declination,

Replace Plan Sheet 64 with Revised Plan Sheet 64A

- Add note for the location of RIPRAP to be installed
- Add note and limits for disposal of excess earth excavation

Replace Plan Sheet 67 with Revised Plan Sheet 67A

- Add detail for riprap, heavy duty erosion control blanket and filter fabric to be installed at the 21" FES. Includes note that states riprap, erosion control blanket and filter fabric shall be incidental to the 21" FES.

Replace Plan Sheet 80 with Revised Plan Sheet 80A

- Expand cross sections to show tie in locations and back slopes

Replace Plan Sheet 81 with Revised Plan Sheet 81A

- Expand cross sections to show tie in locations and back slopes

Replace Plan Sheet 82 with Revised Plan Sheet 82A

- Expand cross sections to show tie in locations and back slopes

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Questions on this addendum may be directed to Chris Groth of Crawford, Murphy & Tilly at 217-787-8050.

**ITEM 752 – CONCRETE CULVERTS, HEADWALLS, AND MISC. DRAINAGE STRUCTURES**

DESCRIPTION

752-1.1 ADD: This item shall consist of installing concrete flared end section and erosion control devices for the pipe under Taxiway C.

MATERIALS

752-1.1

ADD: This item shall consist of installing concrete flared end section and erosion control devices for the pipe under taxiway C.

752-2.2

ADD: RIPRAP – Riprap shall meet the requirements of item 156540 RIPRAP of the standard specifications.

752-2.3

ADD: FILTER FABRIC – Filter fabric shall meet the requirements of item 156540 RIPRAP of the standard specifications.

752-2.4

ADD: EROSION CONTROL BLANKET – Erosion control blanket shall meet the requirements of IDOT standard Specifications for Road and Bridge Construction current addition for Heavy Duty Erosion Control Blanket Article 1081.10(c).

BASIS OF PAYMENT

752-5.1

REVISE: This price shall be full compensation for furnishing all materials and for preparation, excavation, backfilling and placing of materials including riprap, filter fabric and erosion control blankets;

ADD:

Payment will be made under:

Item AR752421 – Precast Reinforced Conc. FES 21” – per each.