

CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER- CONNECT
X0370099	MAST ARM, STEEL, MONOTUBE, 40 FOOT (CDOT)	EACH	1					1	
X0370100	MAST ARM, STEEL, MONOTUBE, 44 FOOT (CDOT)	EACH	2				2		
X0370101	POLE, STEEL, ANCHOR BASE, 11" DIAMETER, 3 GAUGE, 32'-6" (CDOT)	EACH	2				1	1	
X0370102	POLE, STEEL, ANCHOR BASE, 11" DIAMETER, 3 GAUGE, 34'-6" (CDOT)	EACH	1					1	
X0370103	POLE, STEEL, ANCHOR BASE, 12 1/2" DIAMETER, 3 GAUGE, 34'-6" (CDOT)	EACH	5				3	2	
X0370104	RELOCATE EXISTING VIDEO DETECTION CAMERA, COMPLETE (CDOT)	EACH	2				1	1	
X0370105	REMOVE EXSITING TRAFFIC SIGNAL POST OR POLE (CDOT)	EACH	8				4	4	
X0370106	REMOVE CABLE FROM CONDUIT (CDOT)	FOOT	1,066				539	527	
X0370107	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT (CDOT)	EACH	2				1	1	
X0370108	INNERDUCT IN CONDUIT, 1 1/4" (CDOT)	FOOT	532						532
X0370109	FIBER OPTIC HYBRID CABLE IN CONDUIT 6SM/GMM (CDOT)	FOOT	680						680
X0370110	CABINET WORK, SPLICING, TESTING AND MISC. (CDOT)	EACH	2				1	1	
X0370111	GALVANIZED STEEL CONDUIT IN TRENCH, 3-INCH (CDOT)	FOOT	1,178						1,178
X0370112	POLYVINYL CHLORIDE PVC CONDUIT IN TRENCH, 3-INCH (CDOT)	FOOT	162				84	78	
X0370113	TRACER CABLE (CDOT)	FOOT	532						532
X0370114	RACKING CABLES IN MANHOLE OR HANDHOLE (CDOT)	EACH	8				4	4	
X0370115	POLE, STEEL, 32'6", ANCHOR BASE, 11 1/2" B.C., 7 GAUGE (INSTALL ONLY) (CDOT)	EACH	4			4			
X0370116	MAST ARM, STEEL, STREET LIGHTING, 8 FOOT (INSTALL ONLY) (CDOT)	EACH	9			9			
X0370117	MAST ARM, STEEL, STREET LIGHTING, 15 FOOT (INSTALL ONLY) (CDOT)	EACH	4			4			
X0370118	LUMINAIRE, STREET LIGHT, CERAMIC METAL HALIDE, 210 WATT, 240 VOLT, ARTERIAL, SEMI-CUTOFF (INSTALL ONLY) (CDOT)	EACH	15			15			
Z0076600	TRAINEES	HOURL	1000	1000					
X0370119	WIRE, AERIAL, 1/C NO. 6 (CDOT)	FOOT	260			260			
Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOURL	1000	1000					

0
0
2/23

0 0042

- DENOTES SPECIALTY ITEM
- DENOTES CHICAGO DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION

1:27:29 PM
2/22/2013

GRAEF
8501 N. Higgins Road Suite 280
Chicago, Illinois 60631
773 399-0112

USER NAME - 1485	DESIGNED - JSO	REVISED -
PLOT SCALE - 1/8"=1'-0"	DRAWN - NJM	REVISED -
PLOT DATE - 5/22/2013	CHECKED - TNS	REVISED -
	DATE - 03-15-2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

63rd STREET BRIDGE REPLACEMENT - COOK COUNTY
SUMMARY OF QUANTITIES

SCALE: NPS=0' SHEET 8 OF 8 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	1920-B	COOK	137	7E
CONTRACT NO. 60J15			ILLINOIS FED. AID PROJECT	

Rev.