



- NOTES:
1. ANY DISTURBED LANDSCAPING WITHIN THE PLANTER BOX AREAS SHALL BE REPLACED IN KIND, THIS WORK SHALL BE PAID FOR AS LANDSCAPING (SPECIAL).
  2. ALL 8-INCH P.C.C. SIDEWALK SHALL BE HIGH EARLY STRENGTH P.C.C.
  3. FOR ADA CURB RAMP DETAILS, SEE SHEETS 120-123.
  4. LONGITUDINAL CONSTRUCTION JOINT, DRILL AND GROUT NO. 8 DEFORMED EPOXY TIE BARS 30" LONG AT 24" C-C SHALL BE INCLUDED IN THE COST OF THE PCC SHOULDER.

**LEGEND**

- PAVEMENT REMOVAL  
AGGREGATE SUBGRADE IMPROVEMENT, 12"  
PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)
- MEDIAN REMOVAL  
HOT-MIX ASPHALT MEDIAN SURFACE, 4 INCH
- SIDEWALK REMOVAL  
PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH  
(HIGH EARLY STRENGTH)  
DETECTABLE WARNINGS
- SIDEWALK REMOVAL  
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH
- TOPSOIL FURNISH AND PLACE, 4"  
LANDSCAPING, SPECIAL
- COMBINATION CURB AND GUTTER REMOVAL  
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12
- CONCRETE BARRIER REMOVAL  
CONCRETE BARRIER TRANSITION  
BARRIER BASE
- MODIFY CONCRETE BARRIER AND RETAINING WALL  
(REMOVAL AND REPLACEMENT)
- PAVED SHOULDER REMOVAL (DAN RYAN) SEE NOTE 4  
PORTLAND CEMENT CONCRETE SHOULDERS, 14"  
STABILIZED SUB BASE 6"  
SUB BASE GRANULAR MATERIAL, TYPE B-24"  
GEOTECHNICAL FABRIC FOR GROUND STABILIZATION

FILE NAME =	USER NAME = *USER*	DESIGNED - KMM	REVISED -
*FILEL*		DRAWN - LV	REVISED -
	PLOT SCALE = *SCALE*	CHECKED - JDH	REVISED -
	PLOT DATE = *DATE*	DATE - 02-22-2012	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

<b>RESTORATION PLAN</b>			
<b>63RD ST &amp; YALE AVE, 63RD ST &amp; WENTWORTH AVE</b>			
SCALE: 1"=20'	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	1920-B	COOK	137	118
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60J15	