

80% FED. / 20% STATE
CONSTRUCTION CODE

URBAN

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | |
|----------|--|-------|----------------|--------------------------|---------------------------------|
| | | | | ROADWAY 0004 URBAN | BRIDGE 0014 S.N. 049-0087 |
| 50200100 | STRUCTURE EXCAVATION | CU YD | 26 | | 26 |
| 50300100 | FLOOR DRAINS | EACH | 12 | | 12 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 54.6 | | 54.6 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 382.8 | | 382.8 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 935 | | 935 |
| 50300300 | PROTECTIVE COAT | SQ YD | 1551 | | 1551 |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 1990 | | 1990 |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 3080 | | 3080 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 103,520 | | 103,520 |
| 50800515 | BAR SPLICERS | EACH | 126 | | 126 |
| 51100100 | SLOPE WALL 4 INCH | SQ YD | 142 | | 142 |
| 51500100 | NAME PLATES | EACH | 1 | | 1 |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 62.5 | | 62.5 |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 5 | | 5 |

Rev.

• - DENOTES SPECIALTY ITEM

| | | | | | | | | | | | | | |
|---|--|-----------------------|------------------------|---|------------------------------|-------|----|--------|----------------------|----------------------|--------------------|-----------------------|-------------------|
| FILE NAME : I:\6710\6710.24 - IL 43 Over US 41\CADD\ | USER NAME : rggj ADD Sheets\DIGORGI-shc-500.dgn | DESIGNED - DRAWN - | REVISED - REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | | F.A. RTE. 2706 | SECTION 125 HB-BR | COUNTY LAKE | TOTAL SHEETS 51 | SHEET NO. 6 |
| | PLOT SCALE : 100,0000' / 1" | CHECKED - | REVISED - | | SCALE: | SHEET | OF | SHEETS | STA. | TO STA. | CONTRACT NO. 60R61 | | |
| | PLOT DATE : 5/18/2013 | DATE - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | | |