


**TEMPORARY EROSION CONTROL NOTES:**

1. THE CONTRACTOR SHALL INSTALL PERIMETER EROSION BARRIER PRIOR TO STRIPPING OF VEGETATION.
2. DIRECT OR INDIRECT PUMPING OF SEDIMENT-LADEN WATER INTO A STORMWATER FACILITY WITHOUT FILTRATION IS PROHIBITED.
3. RUNOFF FROM EXCAVATED AREAS SHALL LEAVE THE SITE THROUGH SEDIMENT CONTROL DEVICES SHOWN IN IDOT STD. 280001-05, ISHTA STD. K-1, AND/OR NRCS DETAILS FROM 2010 EDITION OF ILLINOIS URBAN MANUAL.
4. ANY PUMPING OR CLEANING OF WATER WITHIN WETLANDS PRIOR TO PLACING SEEDING SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED SEEDING PAY ITEMS.
5. THE CONTRACTOR SHALL SURROUND ANY NECESSARY EARTH STOCKPILES WITH PERIMETER EROSION BARRIER.
6. THE CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AT ALL TIMES. EROSION CONTROL DEVICES SHALL BE INSPECTED EVERY SEVEN CALENDAR DAYS, OR WITHIN 24 HOURS OF PRECIPITATION EQUAL TO OR GREATER THAN 0.5 INCH.
7. THE CONTRACTOR SHALL SEED ALL DISTURBED AREAS AS SOON AS PRACTICAL AFTER CONSTRUCTION ACTIVITIES IN THAT AREA HAVE BEEN CONCLUDED. AREAS THAT HAVE STEEP SLOPES OR WILL NOT RECEIVE PERMANENT LANDSCAPING SHALL BE TEMPORARILY SEEDED. ALL FLATTER AREAS OR AREAS WHERE NO FURTHER WORK IS TO OCCUR FOR 14 DAYS OR MORE, INCLUDING EARTH STOCKPILES, SHALL BE SEEDED AND COVERED WITH EROSION CONTROL BLANKET WITHIN SEVEN (7) CALENDAR DAYS.
8. STOCKPILES OF SOIL OR ANY OTHER BUILDING MATERIALS SHALL NOT BE LOCATED IN SPECIAL MANAGEMENT AREAS SUCH AS WETLANDS.
9. ALL WASTE GENERATED AS A RESULT OF THE PROJECT (INCLUDING DISCARDED BUILDING MATERIALS, CONCRETE TRUCK WASHOUT, CHEMICALS, LITTER, SANITARY WASTE, OR ANY OTHER WASTE) SHALL BE PROPERLY DISPOSED OF AND BE PREVENTED FROM BEING CARRIED OFF THE SITE BY EITHER WIND OR WATER.
10. HEAVY DUTY EROSION CONTROL BLANKET SHALL BE USED FOR COVERING SLOPES STEEPER THAN 3H:1V. TURF REINFORCEMENT MAT WILL BE USED IN AREAS DOWNSTREAM OF PIPE DRAINS, AS SHOWN ON PLAN. EROSION CONTROL BLANKET WILL BE PREFERRED MULCH METHOD IN ALL OTHER AREAS.
11. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS OF ACHIEVING PERMANENT SOIL STABILIZATION. TRAPPED SEDIMENT AND OTHER DISTURBED SOILS RESULTING FROM TEMPORARY MEASURES SHALL BE PROPERLY DISPOSED OF, AND THE AREA PERMANENTLY STABILIZED.

**LEGEND**

- SEEDING, CLASS 4, EROSION CONTROL BLANKET
- PERIMETER EROSION BARRIER
- INLET FILTERS
- TEMPORARY DITCH CHECK
- SEEDING, CLASS 4, TURF REINFORCEMENT MAT
- SEEDING, CLASS 2A, HEAVY DUTY EROSION CONTROL BLANKET
- IMPACTED WETLAND AREA SEEDING, CLASS 4B & 5B



USER NAME = #USER#	DESIGNED - SGL	REVISED -
PLOT SCALE = #SCALE#	DRAWN - SGL	REVISED -
PLOT DATE = #DATE#	CHECKED - FML	REVISED -
	DATE - 02/2012	REVISED -

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2706	125 HB-BR	LAKE	51	16
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60R61	