URBAN

SUMMARY OF QUANTITIES		LOCATION OF WORK		IL 56 (BUTTERFIELD RD) AT AT I-355 SB RAMPS		IL 56 (BUTTERFIELD RD) AT AT I-355 NB RAMPS		INTERCONNECT
		TYPE		TRAFFIC SIGNALS		TRAFFIC SIGNALS		INTERCONNECT
		CODE		0021				
CODE NO.	ITEM	UNIT	TOTAL	90% FED 10% STATE	100% VILLAGE OF DOWNERS GROVE	90% FED 10% STATE	100% VILLAGE OF DOWNERS GROVE	90% FED 10% STATE
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2					2
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2	1		1		
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2,240					2,240
~~87301235~~	~~ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C~~	~~FOOT~~	~~1,580~~	~~675~~		~~905~~		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	9,907	4,668		5,239		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,440	803		637		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	8,520	3,224		5,296		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	71	34		37		
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,612	746		866		
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	8	4		4		
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	4	2		2		
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1			1		
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1	1				
87702220	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 20 FT. AND 38 FT.	EACH	1	1				

13

Rev.

GHA #4085.885

FILE NAME = 60T98-04-500.dgn	USER NAME = jwolfe	DESIGNED - JRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JPW	REVISED -			365	(56R-2) TS	DuPAGE	33	4
	PLOT SCALE = 1:1	CHECKED - KLB	REVISED -					CONTRACT NO. 60T98		
$MODELNAME$	PLOT DATE = 5/8/2013	DATE -	REVISED -		SCALE: NONE SHEET 2 OF 5 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT		