



CONSTRUCTION NOTES:

- ① THE CONTRACTOR SHALL LOCATE AND INTERCEPT THE COUPLING OF THE EXISTING CONDUIT AND SPLICE A NEW GALVANIZED STEEL CONDUIT OF THE SIZE SHOWN. THE WORK SHALL BE INCLUDED IN THE COST OF THE CONDUIT.
- ② CLEAN THE EXISTING HANDHOLE TO REMAIN
- ③ THE CONTRACTOR SHALL REINSTALL THE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT.
- ④ THE CONTRACTOR SHALL REINSTALL THE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT IN THE NEW CONTROLLER CABINET.

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.



RESTORATION OF WORK AREA.
 RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEMS SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME =	USER NAME = gshstn	DESIGNED - JRD	REVISED -
08T10-23-IL 56East Ramp-TS.dgn		DRAWN - PJS/JPW	REVISED -
MODEL NAME =	PLOT SCALE = 1:20	CHECKED - KLB	REVISED -
	PLOT DATE = 5/11/2017	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**TRAFFIC SIGNAL MODERNIZATION PLAN
 IL 56 (BUTTERFIELD RD) AT I-355 NB RAMPS**

F.A.P. RTE. =	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(56R-2) TS		33	23
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60T98	

GHA #4085.885

SCALE: 1"=20' SHEET OF SHEETS STA. TO STA.