

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE 0021					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	47	47				
25200110	SODDING, SALT TOLERANT	SO YD	47	47				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	18	18				
42001300	PROTECTIVE COAT	SO YD	1906	1906				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	434	434				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	12,084	12,084			⚠	
42400800	DETECTABLE WARNINGS	SO FT	292	292				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	434	434				
44000300	CURB REMOVAL	FOOT	341	341				
44000600	SIDEWALK REMOVAL	SO FT	12,084	12,084			⚠	
600000605	CONCRETE CURB, TYPE B	FOOT	341	341				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	107	107				
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	628	628				

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE 0021					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021				
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	1028	1028				

⚠ Rev. 7-17-13

Rev.

FILE NAME	USER NAME	DESIGNED	REVISED
DATE	DATE	CHECKED	REVISED
PLOT SCALE	PLOT DATE	DATE	REVISED

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2013-001-1	COOK	10	3
CONTRACT NO. 60W18			FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT	

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
VARIOUS	2013-001-I	COOK	13	4

CONTRACT: 60W18

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	CONC. CURB, TYPE B (LF)	REMARKS
58th Street and Nagle Avenue	0.0	0.0	0.0	0.0	240.0	0.0	0.0	80.0	0.0	Replace all 4 corners of intersection with ADA Ramps
62nd Street and Kenneth Avenue	0.0	0.0	0.0	0.0	240.0	0.0	0.0	80.0	0.0	Replace all 4 corners of intersection with ADA Ramps
5614 South Austin Avenue	0.0	0.0	0.0	6.0	90.0	0.0	0.0	0.0	0.0	Replace 3 Sidewalk Squares & Service Walk
5712 South Austin Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 6 sidewalk squares
5828 South Austin Avenue	10.0	1.7	1.7	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares and 10 ft of cracked curb
6116 South Austin Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares (tripping hazard)
6651 South Karlov Avenue	0.0	0.0	0.0	0.0	120.0	0.0	0.0	0.0	0.0	Replace 4 sidewalk squares
6644 South Karlov Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6424 South Kedvale	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 damaged sidewalk squares
6212 South Kilbourn Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 6 sidewalk squares
6001 South Kildare Avenue	0.0	0.0	0.0	9.0	0.0	0.0	0.0	0.0	0.0	Replace sinking courtesy walk on 60th Street side
6353 South Kildare	0.0	0.0	0.0	0.0	120.0	0.0	0.0	0.0	0.0	Replace 4 damaged sidewalk squares
6112 South Kilpatrick Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
6509 South Kilpatrick Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 6 sidewalk squares
6002 South Kilpatrick Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
6604 South Kilpatrick Avenue	0.0	0.0	0.0	0.0	30.0	0.0	0.0	0.0	0.0	Replace 1 sidewalk square - tripping hazard
6122 South Knox Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
5535 South Kolin Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares (tripping hazard).
6004 South Kolin Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
6321 South Kolin Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0	Replace 3 sidewalk squares
6338 South Kolin	0.0	0.0	0.0	4.5	0.0	0.0	0.0	0.0	0.0	Replace 1 damaged courtesy walk square closest to street
6805 South Kolin Avenue	0.0	0.0	0.0	0.0	30.0	0.0	0.0	0.0	0.0	Replace cracked sidewalk square
6812 South Kolin Avenue	0.0	0.0	0.0	0.0	120.0	0.0	0.0	0.0	0.0	Replace 4 sidewalk squares
5535 South Kolin Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 1 or 2 sidewalk squares - tripping hazard
5743 South Kolmar	0.0	0.0	0.0	0.0	240.0	0.0	0.0	0.0	0.0	Replace 8 sidewalk squares
6211 South Komensky Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6612 South Komensky Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6534 South Kostner Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares (standing water)
6350 South Lamont Avenue	0.0	0.0	0.0	27.0	0.0	0.0	0.0	0.0	0.0	Replace Courtesy Walk
6339 South Long Avenue	18.0	3.0	0.0	27.0	0.0	0.0	0.0	0.0	0.0	Replace 18 feet of damaged curb and gutter
3841 West Marquette Road	50.0	8.4	0.0	75.0	0.0	0.0	0.0	0.0	0.0	Replace curb and gutter to help alleviate standing water issue, as well as the two sinking walkways (3'6" x 5' and 3' x 5')
3700 West Marquette Road	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
6208 South Mason Avenue	0.0	0.0	0.0	36.0	0.0	0.0	0.0	0.0	0.0	Replace 24 ft of carriage walk
6105 South Massasoit Avenue	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
5653 South McVicker Avenue	0.0	0.0	0.0	45.0	0.0	0.0	0.0	0.0	0.0	Replace 20 ft of carriage walk
6004 South Mobile Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares
5617 South Nagle Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares
<b>SUB-TOTAL</b>	<b>78.0</b>	<b>13.1</b>	<b>1.7</b>	<b>229.5</b>	<b>3570.0</b>	<b>0.0</b>	<b>0.0</b>	<b>160.0</b>	<b>0.0</b>	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**

07-09-13 RP

<b>ROUTE</b>	<b>SECTION</b>	<b>COUNTY</b>	<b>TOTAL SHEETS</b>	<b>SHEET NUMBER</b>
VARIOUS	2013-001-I	COOK	13	8

CONTRACT: 60W18

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	CONC. CURB, TYPE B (LF)	REMARKS
6703 West 59th Street	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares
6707 West 59th Street	0.0	0.0	0.0	9.0	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares and 2 Carriage Walk Squares
6709 West 59th Street	0.0	0.0	0.0	22.5	0.0	0.0	0.0	0.0	0.0	Replace Courtesy Walk and Carriage Walk
6735 West 59th Street	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 Sidewalk Squares on Rutherford Avenue Side of House Adjacent to Tree
6540 West 60th Street	2.0	0.4	0.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace 2 feet of damaged curb
5900 West 63rd Place	0.0	0.0	0.0	0.0	0.0	0.0	350.0	0.0	30.0	Replace Curb and Alley Apron
6031 West 63rd Place	0.0	0.0	0.0	31.5	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares Near East Side of Property and Courtesy Walk. <b>*PLEASE CONFIRM SIDEWALK SQUARES WITH HOMEOWNER FIRST*</b>
4322 West 63rd Street	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
5857-5859 West 63rd Street	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 Sidewalk Squares
3923 West 64th Place	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares (tripping hazard).
5800 West 64th Place	30.0	5.0	5.0	0.0	0.0	0.0	0.0	0.0	0.0	On Menard Avenue side, replace 30 ft of crumbling curb
3900 West 64th Street	7.0	1.2	1.2	0.0	0.0	0.0	0.0	0.0	0.0	Repair 7 feet of daamaged curb (side of home) closest to alley
5914 West 64th Street	2.0	0.4	0.0	3.0	0.0	0.0	0.0	0.0	0.0	Replace 2 feet of damaged curb
6015 West 64th Street	20.0	3.4	3.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace 20 ft of missing and damaged curb.
6158 West 64th Street	0.0	0.0	0.0	0.0	0.0	0.0	30.0	12.0	6.0	Make Alley Handicap/ADA Accessible
4525 West 65th Place	0.0	0.0	0.0	0.0	210.0	0.0	0.0	0.0	0.0	Replace 7 sidewalk squares
4528 West 65th Place	12.0	2.0	0.0	0.0	0.0	0.0	18.0	0.0	0.0	Replace cracked, broken curb and gutter causing standing water issue (entrance of the driveway)
3825 West 66th Street	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 Sidewalk Squares
3911 West 66th Street	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 Sidewalk Squares
3631 West 67th Place	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares (standing water).
3655 West 68th Street	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
3811 West 68th Street	0.0	0.0	0.0	46.5	0.0	0.0	0.0	0.0	0.0	Replace 31 Feet of Cracked, Sunken Catwalk adjacent to curb
3820 West 68th Street	1.5	0.3	0.3	0.0	0.0	0.0	0.0	0.0	0.0	Replace 1.5 Feet of Crumbling Curb
3829 West 68th Street	1.5	0.3	0.3	13.5	0.0	0.0	0.0	0.0	0.0	Replace 1.5 Feet of Crumbling Curb & 9 Feet of Cracked Sinking Catwalk Along
3830 West 68th Street	2.0	0.4	0.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace 2 Feet of Crumbling Curb
3835 West 68th Street	2.0	0.4	0.4	43.5	0.0	0.0	0.0	0.0	0.0	Replace 2 Feet of Cracked, Crumbling Curb & 29 Feet of Sunken, Cracked Catwalk adjacent to curb
3839 West 68th Street	0.0	0.0	0.0	85.5	0.0	0.0	0.0	0.0	0.0	Replace 27 Feet of Cracked, Buckling Catwalk Adjacent to Curb, as well as 3' x 10' service walk, ADA Handicap Accessible
3841 West 68th Street	0.0	0.0	0.0	40.5	0.0	0.0	0.0	0.0	0.0	Replace 27 Feet of Sunken Catwalk Adjacent to Curb
3849 West 68th Street	2.0	0.4	0.0	3.0	0.0	0.0	0.0	0.0	0.0	Replace 2 Feet of Cracked, Crumbling Curb
3854-3858 West 68th Street	10.0	1.7	1.7	0.0	0.0	0.0	0.0	0.0	0.0	Repair 10 ft of curb
3859 West 68th Street	2.0	0.4	0.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace 2 Feet of Crumbling Curb
3735 West 69th Street	0.0	0.0	0.0	0.0	360.0	0.0	0.0	0.0	0.0	Replace 12 sidewalk squares
3828 West 69th Place	0.0	0.0	0.0	0.0	240.0	0.0	0.0	0.0	0.0	Replace 8 sidewalk squares
3916 West 70th Place	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 cracked sidewalk squares
3917 West 70th Place	0.0	0.0	0.0	45.0	0.0	0.0	0.0	0.0	0.0	Replace 2 Sinking Courtesy Walk Squares and 8 Carriage Walk Squares
<b>SUB-TOTAL</b>	<b>94.0</b>	<b>16.3</b>	<b>13.5</b>	<b>343.5</b>	<b>2100.0</b>	<b>0.0</b>	<b>398.0</b>	<b>12.0</b>	<b>36.0</b>	
<b>TOTAL</b>	<b>628.0</b>	<b>106.2</b>	<b>46.5</b>	<b>1104.0</b>	<b>10980.0</b>	<b>0.0</b>	<b>3898.0</b>	<b>292.0</b>	<b>341.0</b>	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**

07-09-13 RP